SE03-010-28W1 Waterflood Pilot

- 1-3 WIW completed in Lodgepole
  - Drilled in 1974, converted immediately to WIW service
  - Served as a pilot injection pattern for Chevron
- Cum WI 3.9MMbbl
  - Equiv. 2.0x PVi or 3.4x HCPVIi
- Modest banked oil response in offset pattern verticals
  - Cum oil 0.27MMbbl, cum water 0.13MMbbl (unallocated)
  - Poor conformance, suspect majority of water went out of zone

Figure 9