



ENBRIDGE PIPELINES (SASKATCHEWAN) INC.

Proposed Manitoba Interconnect Project

14-17-09-28 W1M to 12-16-09-28 W1M

Near Cromer, Manitoba

**Manitoba Innovation, Energy and Mines
Project Application**

File #: CC 13 06

Date: July 7, 2014

A handwritten signature in black ink, appearing to read 'Tom Williams', is written over a horizontal line.

Project Manager

Table of Contents

1.	Background	1
2.	Applicant Information	2
2.1	Technical Qualifications	3
2.2	Financial Qualifications	3
2.2.1	EPSI Qualifications	3
2.2.2	Project Qualifications	3
3.	Project Need	3
4.	Facility/Pipeline Description	4
4.1	Survey and Legal Description	4
4.2	Substance Description	5
4.3	Project Operation	5
4.4	Proposed Project Construction	7
5.	Facility/Pipeline Safety Systems	14
5.1	Corrosion Control	14
5.2	Leak Detection and Emergency Shutdowns	14
6.	Landowner and Occupant Consultations	15
7.	Environment, Health, Safety	18
7.1	Environmental Protection Plan	18
7.2	Emergency Response Plan	18
8.	Other Approvals	18

List of Appendices

Appendix A	Pipeline Right of Way & Facility Survey Plans
Appendix B	Typical Profile and Cross-Sections of Pipeline, Road and Utility Crossings
Appendix C	Pipeline ZML-WV-01 Crossing Plans
Appendix D	Pipeline ZML-VT-01 Crossing Plans
Appendix E	Manitoba Interconnect Project Site Breakdown
Appendix F	Westspur Interconnect Facility Drawings
Appendix G	Bakken Metering Line 26 Receiving Trap Site Drawings
Appendix H	Manitoba Interconnect Facility Drawings
Appendix I	Tundra Delivery Facility Drawings
Appendix J	Direct Landowner and Tenant Line List

1. Background

Enbridge Pipeline (Saskatchewan) Inc. (“EPSI”) is proposing to build the following facilities:

I. Westspur Interconnect Facility

This will be a Greenfield site and requires full development. It will be located adjacent to the Enbridge Pipelines Inc. (EPI) Cromer Terminal and south of EPSI’s NGL Cromer Terminal Lease. This facility will allow EPSI the capability of diverting product from two existing pipelines upstream of EPI’s Cromer Terminal and ultimately transport the product to the Tundra Energy Marketing Limited (Tundra) Cromer Terminal for further shipment. The site will include a new electrical building, a riser for each pipeline, and individual line density measurement speed loops to track product batches for line swings.

II. Manitoba Interconnect Custody Transfer Facility

This will be a Greenfield site and requires full development. It will be located adjacent to EPI’s Cromer Terminal and east of the Bakken Metering Line 26 receiving trap site. This facility will allow EPSI to meter the product prior to final shipment to Tundra’s Cromer Terminal. In addition to the product from the Westspur Interconnect Facility, piping will be installed to connect the directly adjacent Bakken Metering Line 26 pig receiver site to enable the ability to divert Bakken product to the Tundra Cromer Terminal as well. The site will include a sample building, laboratory building, electrical building, skid of three 10” positive displacement meter runs, an 18” ball prover and a 3,000 bbl tank for full flow and thermal relief.

III. Tundra Delivery Facility

This site is located within the confines of the Tundra Cromer Terminal and does not require civil development. This site will allow EPSI to transfer the product to Tundra’s terminal piping. The site will include a pipeline pig receiver, Coriolis meter for line balancing and an electrical building. The EPSI tie-in to Tundra will occur at the end of Tundra’s pipe rack, close to the receiving trap area.

IV. NPS 16 Pipeline

The proposed 16” pipeline, named ZML-WV-01, will run from the Westspur Interconnect Facility at 14-17-09-28 WPM to the Manitoba Interconnect Custody Transfer Facility at 09-17-09-28 WPM. This new pipeline will require new Right-Of-Way and is considered Greenfield. This underground facility will allow the product to be transported to the Manitoba Interconnect Custody Transfer Facility.

V. NPS 12 Pipeline

The proposed 12” pipeline, named ZML-VT-01, will run from the Manitoba Interconnect Custody Transfer Facility at 09-17-09-28 WPM to the Tundra Delivery Facility at 12-16-09-28 WPM. This new pipeline will require new Right-Of-Way and is considered Greenfield. This underground facility will allow the metered product to be transported to Tundra’s Cromer Terminal.

This document will serve as an application to the Manitoba Innovation, Energy and Mines - Petroleum Branch to seek approval for the above noted facilities. The application was prepared in accordance with the following acts and regulations:

- Section 149 (2) of the Oil and Gas Act (applicable to the proposed pipelines and site facilities).

This document provides detailed information regarding the applicant, EPSI; detailed plans and information regarding the proposed Pipelines and Site Facilities; a summary of landowners and occupants correspondence and a summary of other approvals and permits being applied for concurrently.

2. Applicant Information

Enbridge Pipeline (Saskatchewan) Inc. (“EPSI”) owns and operates crude oil and liquids pipeline systems in Southeastern Saskatchewan and Southwestern Manitoba. These systems are comprised of approximately 356 km of trunk line and approximately 1,900 km of crude oil and liquids gathering system pipeline, along with related terminals and storage facilities. The crude oil and natural gas liquids are transported to Cromer, Manitoba and from there to Eastern Canada and the United States via connecting pipeline systems.

2.1 Technical Qualifications

The EPSI Gathering System was built in 1955 to transport Crude Oil and Natural Gas Liquids to Eastern markets. EPSI has many years of experience designing and operating pipeline facilities in a safe and efficient manner.

2.2 Financial Qualifications

EPSI is financially capable to undertake a project of this magnitude and has completed the due diligence to ensure that the project is feasible and that project funding is secured.

2.2.1 EPSI Qualifications

EPSI is part of Enbridge Income Fund Holding Inc. (“EIFH”). EIFH is underpinned by a 50% interest in the Alliance Canada Pipeline, a 100% interest in EPSI and Green Power assets which include a 50% interest in NRGreen Power Limited Partnership and interests in three wind power projects in Western Canada.

2.2.2 Project Qualifications

The Project will be fully backstopped by Tundra under a 5-year Financial Support Agreement (FSA) where Tundra will be responsible for paying to Enbridge a calculated annual revenue requirement based on a Capital Multiplier, which is designed to cover the return of and on the invested capital. Operating expenses will flow through to Tundra as incurred. Beyond the initial contract term of 5 years, Enbridge will pass through any operating costs and maintenance capital associated with the facilities and will earn an operating management fee of 15% of the total cost to provide service on an annual basis.

3. Project Need

In 2012, Tundra Energy Marketing Limited (Tundra) was created to house all of the assets related to blending, terminals and pipelines originally held by Tundra Oil & Gas Limited. Tundra Oil & Gas Limited is a private Winnipeg-based company that engages in the exploration, development, production and marketing of crude oil and natural gas primarily in the Canadian portion of the Williston basin, with core properties located in southwestern Manitoba and southeast Saskatchewan.

The proposed Manitoba Interconnect project will provide a connection from the Enbridge Pipelines (Westspur) Inc. (“EPWI”) and Enbridge Bakken Pipelines Inc. (“EBPI”) systems to the Tundra terminal near Cromer, Manitoba. Once completed, the project will provide the capabilities of delivering segregated batches of Westspur Midale (MSM), South East Sask (SES), or US High Sweet - Clearbrook (UHC) through a single 12” pipeline to Tundra’s Cromer Terminal.

This Manitoba Interconnect project will provide additional demand pull on the EPWI and EBPI pipelines, along with the EPSI Gathering System, during times where long haul export rail-based transportation economics outweigh pipeline alternatives. Offering customers access to a common rail alternative will help preserve EPSI’s market share and encourage volumes to return to the crude oil gathering pipelines. A significant benefit of this project is that it will be able to offer this modal flexibility to its EPWI and EBPI customer base without having to directly charge any incremental toll or incur any capital or volume risk. In addition, any diverted crude oil will allow EPI to transport other products in larger quantities through the EPI Cromer Terminal to Eastern Canadian and U.S. markets.

4. Facility/Pipeline Description

The scope of work the Manitoba Interconnect project includes the development of two greenfield facilities, installation of two new pipelines, installation of assets within Tundra’s Cromer Terminal and modifications to an existing pig receiver site that is owned by EBPI.

4.1 Survey and Legal Description

- I. The proposed Westspur Interconnect Facility will be located at 14-17-09-28 WPM and will be approximately 9,000 m² in size.
- II. A proposed 16” pipeline will originate at the Westspur Interconnect Facility at 14-17-09-28 WPM and terminate at the Manitoba Interconnect Custody Transfer Facility at 09-17-09-28 WPM.
- III. The proposed Manitoba Interconnect Custody Transfer Facility will be located at 09-17-09-28 WPM and will be approximately 19,000 m² in size.
- IV. A proposed 12” pipeline will originate at the Manitoba Interconnect Custody Transfer Facility at 09-17-09-28 WPM and terminate at the Tundra Delivery Facility at 12-16-09-28 WPM.

- V. The proposed Tundra Delivery Facility will be located at 12-16-09-28 WPM (Tundra’s Cromer Terminal) and will utilize Tundra’s existing terminal land for asset placement.

The surveys of the proposed facilities and pipelines will be provided in Appendix A and includes the location of all facility crossings and proximities to the facility area and the pipeline Right-Of-Ways.

4.2 Substance Description

The proposed Manitoba Interconnect Project will transport/divert crude oil produced from North Dakota, southeastern Saskatchewan, and southwestern Manitoba. Current types of crude oil include Westspur Midale (MSM), South East Sask (SES), and US High Sweet - Clearbrook (UCH). See Table 1 for each product’s crude characteristics. Also, all types of crude contain trace amounts of BS&W (Basic Sediments and Water).

Table 1: Substance Description

Product Identifier	Crude Type (Long Name)	Total Sulphur (% by weight)	Pour Point (°C)	Reid Vapour Pressure (kPa)	Density (kg/m ³)	Viscosity (cSt) at Specified Temperature (°C)				
						10.0	20.0	30.0	40.0	45.0
MSM	Westspur Midale	2.30	-3	39.5	877.3	25.0	14.0	8.91	6.55	5.79
SES	South East Sask	1.14	-21	58.7	839.3	6.66	5.05	3.84	3.07	2.78
UHC	US High Sweet - Clearbrook	0.18	-20	74.3	815.0	3.90	3.12	2.53	2.11	1.93

Reference: 2013 Crude Characteristics Booklet (Enbridge)

4.3 Project Operation

The proposed project is expected to have an operating flow rate of 325 m³/hr to 1,100 m³/hr. The flow rate will be dependent on the operating conditions of the entire upstream system and the type of product diverted from Line 23A, Line 23B, or Line 26. See Table 2 for the anticipated flow rates from each of the main pipelines.

Table 2: Pipeline Flow Rate Ranges

Pipeline	Min. Flow (m ³ /hr)	Max. Flow (m ³ /hr)	Avg. Flow (m ³ /hr)
23A (16")	350	1,100	900
23B (12")	325	650	350
26 (16")	325	1,100	750

The design of the project does not include any type of pumps to assist the delivery of the products to Tundra's Cromer Terminal. As a result, the two newly proposed facilities and the two newly proposed pipelines are designed to ensure that a minimum delivery pressure of 50 psi can be achieved to overcome the back pressure that is created by Tundra's facilities.

The main function of the Westspur Interconnect Facility at 14-17-09-28 WPM is to enable the capability to divert products from EPWI's two main pipelines, Line 23A and Line 23B, and transfer the product to the proposed 16" pipeline, ZML-WV-01. The products will be diverted from the main lines via actuated control valves, which will be installed on the new risers. The control valves will be operated by Enbridge's Control Centre, which is based in Edmonton, Alberta. The diverted product, or batched swings, will be monitored by individual line density measurement speed loops. The product will flow past the speed loops, with a small amount of the product diverted and flowing through the speed loop. The speed loops will analyze the product's density, which will identify the specific crude product. The speed loops are the main tools for the Control Centre to identify and control the different batches being diverted to Tundra's Cromer Terminal.

The main function of the Manitoba Interconnect Custody Transfer Facility at 09-17-09-28 WPM is to meter the product that is being transferred to Tundra's Cromer Terminal, sample the products for their crude characteristics and BS&W content, and provide full flow and thermal pressure relief for emergency situations. The 3,000 bbl tank can also provide pressure and product relief for maintenance type work at the facility. SES and MSM products will enter the facility via pipeline ZML-WV-01 and, the UHC product will enter the facility via piping that connects the proposed facility to the existing Bakken Metering Line 26 Pig Receiving Site. The products will first flow through the automated sample building, where samples of the product will be taken automatically during shipment. The sample jugs will be carried to the on-site laboratory building by EPSI operations personnel, where the product will be analyzed for its crude characteristics and BS&W content. Sampling of the product is critical in order to verify the type of product being shipped and to document the BS&W content. The product will flow from the sample building to the meter skid, where the product will be metered for custody transfer purposes. The meter skid is designed for the expected flow rates and contains three 10" PD meters. The flow of product through the three meters will be controlled by control valves, where any combination of the three meters can be in operation depending on the flow rate. The PD meters will measure and record the volume of product throughput and provide the necessary documentation for transferring the custody of the product to Tundra. Next, the product will either flow from the meter skid to the ball prover or to the 12" pig launcher (ZML-VT-01). The purpose of the ball prover

is to prove that the PD meters are measuring the volume accurately, and within tolerances. The prover will be used to individually prove each of the PD meters as often as required, which will be set out by the Enbridge Measurement department.

The main function for EPSI's assets on Tundra's Cromer Terminal (Tundra Delivery Facility) is to ultimately transfer the products to Tundra's tankage. The products will enter the facility via the 12" pipeline ZML-VT-01. The products will then flow through a Coriolis meter before being transferred to Tundra. The Coriolis meter will measure the volume throughput and ensure that the pipelines are balanced, providing leak detection capabilities.

The proposed facilities and pipelines will be continuously flooded with one of the three transported products. The daily flow rates will fluctuate, as per Table 2, and be solely dependent on monthly volumes nominated by Tundra.

4.4 Proposed Project Construction

I. Westspur Interconnect Facility

The Westspur Interconnect Facility site is a Greenfield location and will be approximately 9,000 m² in area. The site requires full development and will be an added new site for EPSI operations to manage. Prior to installment of the buildings and equipment on site, the site will be developed first by removing all top soil and levelling the ground with compacted lifts of clay and gravel, as per site design referenced by the geotechnical report. Next, a combination of screw and driven piles will be installed as per specified locations. Piles will be driven to provide a foundation support for the proposed electrical building and a combination of driven and screw piles will be installed for pipe and equipment supports.

The electrical building (ESB) will be pre-fabricated in a shop with the electrical wiring and components pre-installed, as per the latest edition of the Canadian Electrical Code (CEC). The completed ESB will be mobilized to site and installed on the specified piles. An electrical feeder cable will be installed below grade from the ESB to Manitoba Hydro's service system, with the electrical service being 400A. The ESB will provide service for the facility lighting, pressure transmitters, automatic valves, and associated instrumentation and equipment.

Two pipeline risers will be installed on site, one for the 12" ZML-AC-01 (Line 23B) and one for the 16" ZML-AC-02 (Line 23A). These risers will allow EPWI to install

control equipment to divert products from the EPWI main line pipelines to the new 16" pipeline ZML-WV-01 that is to be constructed as part of this project. The riser bends will be pre-bent through a hot induction bending process at the manufacturer's facility. The portion of the risers that requires to be tied-in below grade will be coated with Fusion Bonded Epoxy (FBE). The above grade portion of the risers will be painted as per EPSI's coating specs to mitigate corrosion. See drawing #s D-MIW-420 SHT. 1 and D-MIW-420 SHT. 2 for the riser designs and instrumentation details. The risers will be constructed with CSA Z245.1, Grade 359, Cat. II line pipe. The wall thicknesses for the 16" and 12" risers will be 9.5 mm. The risers will be tested for an MOP of 7,380 kPa, with a maximum test pressure of 11,512 kPa and a minimum test pressure of 11,070 kPa. The tests will be conducted as 1 hour visual hydrostatic pressure tests in shop and will be installed pre-tested.

In addition to the above proposed facility assets, the site will also include the 16" pipeline ZML-WV-01 pig launcher and two line density measurement speed loops. The pig launcher will be designed to the MOP of the pipeline and the test pressure limits, see subsection 4.1.3.IV for more details on the pipeline. See drawing # D-MIW-420 SHT. 3 for the pig launcher design details. The line density measurement speed loops will consist of a 1" Coriolis mass meter, globe valve, and ball valves for isolation.

The remaining facility assets to be installed on site are the facility piping and fittings, the stairs and platforms for the risers, the perimeter fence, facility berm and access to site. The facility piping and fittings will connect the products from Lines 23A and 23B to the speed loops, and ultimately to the ZML-WV-01 pig launcher. The piping and fittings will be designed for a MOP of 7,380 kPa, with a maximum hydrostatic test pressure of 11,512 kPa and a minimum test pressure of 11,070 kPa. The piping and fitting material will consist of ASME material. The stairs and platforms will be pre-fabricated as per Enbridge Design Standard D05-401: Platforms, Stairs, and Ladders, and will be erected on site prior to commissioning of facility. The perimeter fence will also be installed prior to commissioning activities to maintain the facility's security. A berm will be constructed around the facility, situated on the inside of the perimeter fence. The berm will consist of compacted clay and gravel. Lastly, an access ramp to the facility site will be constructed of compacted clay and gravel, in order to access the site over the facility berm. A rolling gate will be installed at the access ramp location. See drawing # D-MIW-410 SHT. 1 for the overall design layout of the facility site.

II. Manitoba Interconnect Custody Transfer Facility

The Manitoba Interconnect Custody Transfer Facility site is a Greenfield location and will be approximately 19,000 m² in area. The site requires full development and will be an added new site for EPSI operations to manage. Prior to installment of the buildings and equipment on site, the site will be developed first by removing all top soil and levelling the ground with compacted lifts of clay and gravel, as per site design referenced by the geotechnical report. Next, a combination of screw and driven piles will be installed as per specified locations. Piles will be driven to provide a foundation support for the proposed facility buildings and a combination of driven and screw piles will be installed for pipe and equipment supports. Once the site is developed, a sample building, a laboratory building, an ESB, skid containing three PD meter runs, a ball prover and a 3,000 bbl tank will be installed.

The ESB will be fabricated in a shop with the electrical wiring and components installed as per the latest edition of the CEC. The completed ESB will be delivered to site and installed on the specified piles. An electrical feeder cable will be installed below grade from the ESB to Manitoba Hydro's service system to provide a 400 amp service. The ESB will provide service for the facility lighting, pressure transmitters, automatic valves, sample building, laboratory building and associated instrumentation and equipment.

The laboratory and sample buildings will also be fabricated in a shop with the building's electrical and mechanical components installed. They shall be wired as per the latest edition of the CEC. The buildings will then be delivered to site and installed on the specified piles.

The three positive displacement (PD) meter runs will be installed on a meter skid that will be pre-fabricated in shop. The meter skid will consist of a skid platform, three individual meter runs, associated inlet and outlet manifolds, and will be fitted for electrical and network cables to be connected to the meter run equipment and instrumentation. The PD meters will be the 10" FMC model JB10-S6 designed for ANSI 300 service. The piping and fittings will consist of ASME material and be hydrostatically tested for a MOP of 4,960 kPa. The maximum test pressure will be 7,737 kPa and the minimum test pressure will be 7,440 kPa. The fabricated meter skid will be transported to site in two sections and assembled on the specified piles.

The ball prover will be fabricated in the manufacturer's shop and will be sold as a complete unit on a skid base. The ball prover will be designed to fit an 18" stainless steel sphere ball, which will be used to prove the proposed 10" PD meters. The ball prover skid will consist of 18" piping in the shape of a "U" with the ends of the "U" consisting of oversized 24" pipe, an internal stopper for the ball, four way valve, and inlet and outlet piping. The piping will consist of ASME material and be rated for ANSI 300 service. The ball prover will be capable of proving the full rated capacity of an individual PD meter. The skid unit will be shipped from the manufacturer and installed on the specified piles. See drawing # D-MIC-420 SHT. 4 for the ball prover design details.

The 3,000 bbl storage tank will be completely fabricated off-site at the manufacturer's shop. The tank will be approximately 24 ft. in diameter and 44 ft. in height. The tank will be constructed as per the current edition of API 650 and installed as per the current edition of the National Fire Code of Canada. The tank will be situated within a tank containment berm. The tank berm will consist of steel berm walls approximately 3 ft. high from ground level with a high density polyethylene (HDPE) liner that covers the entire area of the berm and will be bolted to the inside of the berm walls. The HDPE liner will be installed in sections and welded together by fusing the individual liner sheets. The proposed berm will have an approximate containment volume of 700 m³. Driven piles will be installed as the tank's foundation, along with a steel tank base. The tank will be delivered from the manufacturer as a whole unit and installed on the steel base. An internal floating roof will be installed on site. A common tank line will connect the tank to the facility's piping system and will accommodate full flow and thermal relief. The tank line will consist of ASME material and will be 10" in diameter, hydrostatically tested for an MOP of 4,960 kPa. Electrical cables will be installed from the ESB to the tank for servicing the tank mixer, radar gauge, and level switch. Lastly, gravel will be placed inside the berm, on top of the HDPE liner, in order to protect the berm liner.

In addition to the above proposed facility assets, the site will also include the pipeline ZML-WV-01 pig receiver and the pipeline ZML-VT-01 pig launcher. The pig receiver will be designed to the MOP of the pipeline and the expected test pressure limits, see subsection 4.1.3.IV for more details on pipeline ZML-WV-01. The pig launcher will be designed to the MOP of the pipeline and the expected test pressure limits, see subsection 4.1.3.V for more details on pipeline ZML-VT-01. See drawing # D-MIC-420 SHT. 1 for the ZML-WV-01 pig receiver design details and drawing # D-MIC-420 SHT. 5 for the ZML-VT-01 pig launcher design details.

The remaining facility assets to be installed on site are the facility piping and fittings, the stairs and platforms for accessing valves, and the perimeter fence. The piping and fittings will be designed for a MOP of 4,960 kPa, with a maximum hydrostatic test pressure of 7,737 kPa and a minimum test pressure of 7,440 kPa. The piping and fitting material will consist of ASME material. The stairs and platforms will be fabricated as per Enbridge Design Standard D05-401: Platforms, Stairs, and Ladders, and will be erected on site prior to commissioning of facility. The perimeter fence will also be installed prior to commissioning activities to maintain the facility's security. The facility will be developed by an existing access road, therefore no approaches or roads will need to be constructed. The perimeter fence will have two rolling gates to allow traffic into the facility as well as through to the Bakken Metering Line 26 Receiving Trap Site. See drawings D-MIC-410 SHT. 1 and D-CBK-410 SHT. 1 for the overall design layout of the facility.

In order to tie-into Line 26, rework must be completed at the Bakken Metering Line 26 Receiving Trap site. All work on assets associated with EBPI falls under regulatory jurisdiction of the NEB and a Section 58 Streamlining Order is being completed for said activities. EPSI will take custody of the crude and will own assets as soon as the crude is diverted off of the Bakken Metering Line 26 Receiving Trap piping. There will be approximately 130 m of buried piping that will connect the Bakken Metering Line 26 Receiving Trap site to the Manitoba Interconnect Custody Transfer Facility. This will be a 16" line that will be designed for a MOP of 9,930 kPa, with a minimum hydrostatic test pressure of 14,892 kPa and a maximum hydrostatic test pressure of 15,485 kPa. The piping will be constructed of Grade 359 CAT II NPS 16 steel pipe (406.4 mm OD) x 9.5 mm wall thickness, and will be coated with Fusion Bonded Epoxy (FBE). See drawing D-CBK-410 SHT. 1 for the plot plan of the Bakken Line 26 pig receiver site, see D-CBK-420 SHT. 1D for the Bakken Line 26 pig receiver demolition drawing and see D-CBK-420 SHT. 1 for the Bakken Line 26 pig receiver installation drawing.

III. Tundra Delivery Facility

The Tundra Delivery Facility will be constructed within the confines of Tundra's Cromer Terminal, which is owned and operated by Tundra. Therefore this site does not require civil development. The 12" ZML-VT-01 pipeline will enter Tundra's facility near the proposed receiver trap location, directly adjacent to Tundra's current pipeline header area. EPSI assets to be installed at the Tundra facility are the ZML-VT-01 pig receiver, a Coriolis meter, an ESB and associated

pipings and fittings. See drawing D-MIT-410 SHT. 1 for the plot plan of EPSI's assets at the Tundra Delivery Facility.

The ESB will be fabricated in a shop with the electrical wiring and components installed, as per the latest edition of the CEC. The completed ESB will be delivered to site and placed and installed on the specified piles. Tundra will run an electrical feeder cable from their current service to the EPSI ESB in order to provide EPSI with the required electrical load. The ESB will provide service for the automated valves on site, the Coriolis meter, and the associated instrumentation.

The pipeline ZML-VT-01 pig receiver will be designed to the MOP of the pipeline and test pressure limits, see subsection 4.1.3.V for more details on the pipeline. See drawing D-MIT-420 SHT. 1 for the ZML-VT-01 pig receiver design details.

The remaining facility assets to be installed on site are the facility piping, fittings, and the Coriolis meter. The piping and fitting material will consist of ASME material. The piping and fittings will be designed for a MOP of 4,960 kPa, with a maximum hydrostatic test pressure of 7,737 kPa and a minimum test pressure of 7,440 kPa.

IV. 16" Pipeline (ZML-WV-01)

The total length of the proposed ZML-WV-01 pipeline will be approximately 1,200 metres and will include five (5) third-party pipeline crossings and one (1) third-party road crossing. The pig launcher will be installed above grade at the Westspur Interconnect Facility and a pig receiver will be installed above grade at the Manitoba Interconnect Custody Transfer Facility. Drawings such as the pipeline route/design, typical pipeline profile, cross-section of pipeline installation, and pipeline, road, and buried cable crossing typicals are provided in Appendix B. The pipeline will be constructed using generally accepted installation practices, as per CSA Z662-11, with the pipeline having a minimum depth of cover of 1.5 m. The pipeline construction method will include both boring and trenching. EPSI will acquire the necessary crossing agreements and ensure that there is a minimum of 0.3 m cover between the proposed pipeline and third-party utilities. Pipeline construction will also adhere to conditions as outline in the environmental assessment approval by Manitoba Conservation.

The pipeline is proposed to be constructed of NPS 16 steel pipe. Specifically, the pipe will be 406.4 mm (OD) x 9.5 mm (WT) and will be constructed of Grade 359, Category II, FBE coated steel line pipe as per CSA regulation Z245.1 – Steel Line Pipe. The pipeline is designed for a 7,380 kPa MOP. The pipeline will be hydrostatically tested for 8 hours immediately following installation with a maximum test pressure of 11,512 kPa and a minimum test pressure of 11,070 kPa. The hydrostatic test will consist of a 4 hour strength test and a 4 hour leak test, as per CSA Z662-11 – Oil & Gas Pipeline Systems. See the pipeline construction alignment sheet SM-0112-13-3-CON-R2.

V. 12" Pipeline (ZML-VT-01)

The total length of the proposed ZML-VT-01 pipeline will be approximately 350 metres and will include three (3) third-party pipeline crossings, one (1) third-party road crossing, seven (7) third-party buried cable crossings, and three (3) third-party overhead electrical cable crossings. The pig launcher will be installed above grade at the Manitoba Interconnect Custody Transfer Facility and the pig receiver will be installed above grade at the Tundra Delivery Facility. Drawings such as the pipeline route/design, typical pipeline profile, cross-section of pipeline installation, and pipeline, road, and buried cable crossing typicals are provided in Appendix B. The pipeline will be constructed using generally accepted installation practices, as per CSA Z662-11, with the pipeline having a minimum depth of cover of 1.5 m. The pipeline construction method will include both boring and trenching. EPSI will acquire the necessary crossing agreements and ensure that there is a minimum of 0.3 m cover between the proposed pipeline and third-party utilities. Pipeline construction will also adhere to conditions as outline in the environmental assessment approval by Manitoba Conservation.

The pipeline is proposed to be constructed of NPS 12 steel pipe. Specifically, the pipe will be 323.9 mm (OD) x 7.1 mm (WT) and will be constructed of Grade 359, Category II, FBE coated steel line pipe as per CSA regulation Z245.1 – Steel Line Pipe. The pipeline is designed for a 4,960 kPa MOP. The pipeline will be hydrostatically tested for 8 hours immediately following installation with a maximum test pressure of 7,737 kPa and a minimum test pressure of 7,440 kPa. The hydrostatic test will consist of a 4 hour strength test and a 4 hour leak test, as per CSA Z662-11 – Oil & Gas Pipeline Systems. See the pipeline construction alignment sheet SM-0112-13-4-CON-R2.

5. Facility/Pipeline Safety Systems

The design of this project will incorporate corrosion control, leak detection and pressure relief.

5.1 Corrosion Control

The two proposed pipelines will be constructed with line pipe that is externally coated with FBE. All girth welds below grade will also be coated with FBE. The piping and fittings above grade at all three facilities will be primed and painted as per Enbridge Construction Specification FCS019 – External Paint to Enbridge paint standard P-210. The two proposed pipelines will also be pigged at regular intervals to remove paraffins and waxes that may cause corrosion on the interior of the pipeline. In addition, both pipelines and the buried segment of 16” pipe that connects the Bakken Metering Line 26 Pig Receiving Site to the Manitoba Interconnect Custody Transfer Facility will have cathodic protection (CP). The proposed corrosion control system will comply with CSA Z662-11 – Oil & Gas Pipelines Systems.

5.2 Leak Detection and Emergency Shutdowns

EPSI intends to have a robust leak prevention and detection system in place along with an Emergency Shutdown plan for each facility and pipeline. The proposed plan will include the following:

- Installation and monitoring of a Coriolis meter at the Tundra Delivery Facility. The meter will measure any deviations to the output volume and can be compared to other meters on the Enbridge system as required. This will be completed via the ATMOS leak detection program.
- Pigging of the pipelines at regular intervals to remove any build up of potentially corrosive material in the pipeline. Pigging schedules will be developed by EPSI operations.
- Pressure Indicating Transmitters (PITs) installed at each facility to monitor the pressures and pressure drops.
- Control Centre in Edmonton will have the capability of shutting down all facilities via control valves, in case of an emergency.
- Operation personnel on site can also shut down the facilities, in case of an emergency.

6. Landowner and Occupant Consultations

The consultation program for this Project was designed and implemented to ensure all potentially affected parties were engaged and provided with detailed and timely information regarding the Project.

DESIGN & IMPLEMENTATION OF THE CONSULTATION PROGRAM

Through experience gained from other projects in the Southwestern Manitoba area, the anticipated impacts on stakeholders were identified and assessed to determine expected levels and areas of public interest in the Project. EPSI also took into account the nature and type of work to be undertaken as part of the construction and operation of the Project. An appropriate consultation program was then designed. The following is a list of the drivers that influenced the design of the consultation program:

- The Project work proposed is modest in scope, the nature, magnitude and potential impacts associated with the Project are not expected to be extensive or long-lasting.
- The Project's impacts with respect to construction noise, dust, traffic, and disruptions due to equipment movement are expected to be low. There will be an increase in noise arising from construction activities, such as pile installation, but in short intervals and will cease upon completion of activity and construction.
- At any given time, the work force on each site will not exceed twenty people. The Project will have a negligible impact on local infrastructure (such as roads, power utilities, water, and solid waste facilities) and on local services (such as accommodation, recreation, emergency and health care).
- The construction crews will be working no more than six days a week, during daylight hours; the construction window may be up to 8 months.
- Enbridge has typically had positive relationships with local landowners and regional stakeholders.
- There is a significant amount of oil and gas development taking place in this area, which means the landowners are sensitized to development of this nature.

STAKEHOLDER GROUPS CONSULTED & METHOD OF CONSULTATION

The following stakeholders have been identified by EPSI as being potentially affected by the Project:

DIRECTLY IMPACTED LANDOWNER

There is one tenant on Enbridge property where the Project is proposed.

- EPSI has and will continue to consult personally with this tenant. Tenant consent has been discussed and acquired.

PRIMARY STAKEHOLDER GROUPS

Landowners and Tenants within a 1.5 km radius of the tie-in points and 0.5 km distance along the centerline of the pipeline.

- Project information packages were mailed to the respective landowners and tenants, within the radii mentioned above.

OTHER STAKEHOLDERS GROUPS – potentially affected

RM of Pipestone

- Project information packages were emailed (same packages that were sent to landowners and tenants).
- EPSI is currently in the process of obtaining RM of Pipestone's approval.

SUMMARY OF COMPLETED ACTIVITIES & RESULTS

ACTIVITY	TIMING	DETAILS	ISSUES AND/OR CONCERNS RAISED
Face-To-Face Visit with all directly impacted landowners and tenant	Completed on May 17 th , 2014	<p>An EPSI land agent met with the directly impacted tenant to discuss the Project details, answer questions, and address any potential concerns.</p> <p>During this meeting, the land agent also secured the Grant of Consent of Lessee Agreement for the Project.</p>	The tenant had no issues or concerns with the Project.
Mailed project information packages to landowners and tenants within a 1.5 km radius of the tie-in points and 0.5 km from the centerline of the pipeline	Completed on May 12 th , 2014	A description of the Project scope and a map of the proposed project area were sent by regular mail to the adjacent landowners located within the radii established by the Manitoba Innovation, Energy and Mines – Petroleum Branch.	To date no issues or concerns have been raised.
RM of Pipestone Approval	In Progress	EPSI is currently pursuing approval from the RM for the Project.	No issues or concerns have been raised to date.
	Completed on May 12 th , 2014	The same Project information package that was mailed to the adjacent landowners and tenants was also mailed to the RM.	No issues or concerns were raised.

7. Environment, Health and Safety

EPSI will utilize standard practices, existing manuals and procedures, as well as project specific plans and procedures during the construction of the facilities and over the course of operation.

7.1 Environmental Protection Plan

EPSI will utilize company manuals (Environmental Guidelines for Construction, Waste Management Plan, Environmental Protection Plan, and Vegetation Management Plan) and procedures (Operating and Maintenance Procedures) to develop this project in an environmentally responsible manner. Relevant topics included in our documents include, but not are limited to:

- Site and right of way access
- Erosion and silt control
- Topsoil salvage
- Pipeline installation techniques
- Trench (Bell hole) water management
- Vegetation, habitat, and wildlife protection measures
- Environmental inspection
- Reclamation
- Spill reporting
- Emergency mitigation procedures

7.2 Emergency Response Plan

A site-specific Emergency Response Plan will be developed for the construction of the pipelines and facilities, and will include the nearest hospital, emergency service numbers, and a map for specific emergency routes to and from the construction location.

8. Other Approvals

In addition to the Petroleum Branch approval, EPSI is either concurrently seeking or intends to seek the additional approvals and permits outlined below.

Manitoba Conservation

EPSI will be notifying Manitoba Conservation with an Environmental Overview (EO) of the Project concurrently with this application. EPSI expects that an Environmental Licence will not be required for this Project.

Manitoba Infrastructure and Transportation

EPSI intends to notify Manitoba Infrastructure and Transportation of the proposed highway crossing and obtain the required approval(s).

Other Utilities and Right of Ways

EPSI intends to notify and obtain required crossing and proximity agreements for all utilities and existing rights of way.

Affected Municipalities

EPSI intends to notify and obtain required approvals from the RM of Pipestone for the proposed project.

Department of Municipal Affairs, Culture and Housing (Heritage Branch)

Should any archeological sites along the pipeline right of ways or facility boundaries be identified through desktop reviews of available information, EPSI will seek the necessary approvals to install the proposed pipelines and facilities.



Appendix A
Pipeline Right of Way &
Facility Survey Plans

Drawing Name	Drawing Number
16" (ZML-WV-01) Pipelines Construction Alignment	SM-0112-13-3-CON-R2
12" (ZML-VT-01) Pipelines Construction Alignment	SM-0112-13-4-CON-R2
Westspur Interconnect Facility Lease IOP	SM-0112-13-1-IOP-1-R2
Westspur Interconnect Facility Lease IOP	SM-0112-13-1-IOP-2-R2
Manitoba Interconnect Facility Lease IOP	SM-0112-13-2-IOP-1-R2
Manitoba Interconnect Facility Lease IOP	SM-0112-13-2-IOP-2-R2

STATION TO STATION	DISTANCE (Meters)	R.O.W Width	AREA (Hectares)	LEGAL DESCRIPTION	OWNER
0+000.00 - 0+120.197	120.197	5.0	0.15	NE 1/4, Sec 16-28 W P M	INTERPROVINCIAL PIPELINE INC.
0+165.597 - 0+194.528	153.591	5.0	0.07	NW 1/4, Sec 16-28 W P M	TUNDRA ENERGY MARKETING LIMITED

BOOK OF REFERENCE	
STATION TO STATION	DISTANCE (Meters)
0+000.00 - 0+120.197	120.197
0+165.597 - 0+194.528	153.591

CROSSING / REFERENCE DRAWINGS			
No.	DESCRIPTION	LOCATION	DRAWING No.
1	12" ENBRIDGE GAS LINE (MONTROSA HYDRO)	NE 1/4, Sec 17	SM4112-13-4-0002-01
2	4" MBE HYDRO LINE (MONTROSA HYDRO)	NE 1/4, Sec 17	SM4112-13-4-0002-02
3	2" BURIED WTE CABLES	NW 1/4, Sec 18	SM4112-13-4-0002-03
4	4.57' ROAD - PLAN No 1753 BLD TO PARKER HIGHWAY No 258	NW 1/4, Sec 18	SM4112-13-4-0002-04
5	BURIED WTE CABLE	NW 1/4, Sec 19	SM4112-13-4-0002-05
6	3" WIRE HYDRO LINE (MONTROSA HYDRO)	NW 1/4, Sec 19	SM4112-13-4-0002-06
7	3" BURIED WTE CABLES (2" WTE + 1" WTE)	NW 1/4, Sec 18	SM4112-13-4-0002-07
8	3" BURIED WTE CABLES (2" WTE + 1" WTE)	NW 1/4, Sec 18	SM4112-13-4-0002-08
9	BURIED WTE CABLE	NW 1/4, Sec 18	SM4112-13-4-0002-09
10	BURIED WTE CABLE	NW 1/4, Sec 18	SM4112-13-4-0002-10
11	BURIED WTE CABLE	NW 1/4, Sec 18	SM4112-13-4-0002-11
12	BURIED WTE CABLE	NW 1/4, Sec 18	SM4112-13-4-0002-12
13	BURIED WTE CABLE	NW 1/4, Sec 18	SM4112-13-4-0002-13

REVISION / ISSUED			
No.	DATE	DESCRIPTION	ISSUED TO
1	2016	ISSUED FOR PERMITTING	ENVIRONMENTAL
2	2017	REVISED PERMITTING	ENVIRONMENTAL
3	2017	REVISED PERMITTING	ENVIRONMENTAL
4	2017	REVISED PERMITTING	ENVIRONMENTAL
5	2017	REVISED PERMITTING	ENVIRONMENTAL
6	2017	REVISED PERMITTING	ENVIRONMENTAL
7	2017	REVISED PERMITTING	ENVIRONMENTAL
8	2017	REVISED PERMITTING	ENVIRONMENTAL
9	2017	REVISED PERMITTING	ENVIRONMENTAL
10	2017	REVISED PERMITTING	ENVIRONMENTAL
11	2017	REVISED PERMITTING	ENVIRONMENTAL
12	2017	REVISED PERMITTING	ENVIRONMENTAL
13	2017	REVISED PERMITTING	ENVIRONMENTAL
14	2017	REVISED PERMITTING	ENVIRONMENTAL
15	2017	REVISED PERMITTING	ENVIRONMENTAL
16	2017	REVISED PERMITTING	ENVIRONMENTAL
17	2017	REVISED PERMITTING	ENVIRONMENTAL
18	2017	REVISED PERMITTING	ENVIRONMENTAL
19	2017	REVISED PERMITTING	ENVIRONMENTAL
20	2017	REVISED PERMITTING	ENVIRONMENTAL
21	2017	REVISED PERMITTING	ENVIRONMENTAL
22	2017	REVISED PERMITTING	ENVIRONMENTAL
23	2017	REVISED PERMITTING	ENVIRONMENTAL
24	2017	REVISED PERMITTING	ENVIRONMENTAL
25	2017	REVISED PERMITTING	ENVIRONMENTAL
26	2017	REVISED PERMITTING	ENVIRONMENTAL
27	2017	REVISED PERMITTING	ENVIRONMENTAL
28	2017	REVISED PERMITTING	ENVIRONMENTAL
29	2017	REVISED PERMITTING	ENVIRONMENTAL
30	2017	REVISED PERMITTING	ENVIRONMENTAL
31	2017	REVISED PERMITTING	ENVIRONMENTAL
32	2017	REVISED PERMITTING	ENVIRONMENTAL
33	2017	REVISED PERMITTING	ENVIRONMENTAL
34	2017	REVISED PERMITTING	ENVIRONMENTAL
35	2017	REVISED PERMITTING	ENVIRONMENTAL
36	2017	REVISED PERMITTING	ENVIRONMENTAL
37	2017	REVISED PERMITTING	ENVIRONMENTAL
38	2017	REVISED PERMITTING	ENVIRONMENTAL
39	2017	REVISED PERMITTING	ENVIRONMENTAL
40	2017	REVISED PERMITTING	ENVIRONMENTAL
41	2017	REVISED PERMITTING	ENVIRONMENTAL
42	2017	REVISED PERMITTING	ENVIRONMENTAL
43	2017	REVISED PERMITTING	ENVIRONMENTAL
44	2017	REVISED PERMITTING	ENVIRONMENTAL
45	2017	REVISED PERMITTING	ENVIRONMENTAL
46	2017	REVISED PERMITTING	ENVIRONMENTAL
47	2017	REVISED PERMITTING	ENVIRONMENTAL
48	2017	REVISED PERMITTING	ENVIRONMENTAL
49	2017	REVISED PERMITTING	ENVIRONMENTAL
50	2017	REVISED PERMITTING	ENVIRONMENTAL

WELL LEGEND:

- GAS INJECTION WELL
- SUSPENDED WELL
- ABANDONED WELL
- SUSPENDED GAS WELL
- ABANDONED GAS WELL
- WATER SOURCE WELL

PIPE SPECIFICATIONS:

CARRIED OVER BY 15.24 M (50 FT) OVER 3.7 M (12 FT) WIDE R.O.W.

Location: NE 1/4, Sec 16, T20S, R16W, S18

Line: Enbridge Gas Line (Montrosa Hydro)

Material: Steel, 100 mm dia, 10 MPa

Operating Pressure: 4000 kPa

Project Category: Class 01

LEGEND:


- Survey Monument (shown as a circle with a cross)
- 0.25 x 0.25 m (10" x 10") iron plate shown thus
- 0.15 x 0.15 m (6" x 6") iron plate shown thus
- 0.10 x 0.10 m (4" x 4") iron plate shown thus
- 0.05 x 0.05 m (2" x 2") iron plate shown thus
- 0.025 x 0.025 m (1" x 1") iron plate shown thus
- 0.0125 x 0.0125 m (0.5" x 0.5") iron plate shown thus
- 0.00625 x 0.00625 m (0.25" x 0.25") iron plate shown thus
- 0.003125 x 0.003125 m (0.125" x 0.125") iron plate shown thus
- 0.0015625 x 0.0015625 m (0.0625" x 0.0625") iron plate shown thus
- 0.00078125 x 0.00078125 m (0.03125" x 0.03125") iron plate shown thus
- 0.000390625 x 0.000390625 m (0.015625" x 0.015625") iron plate shown thus
- 0.0001953125 x 0.0001953125 m (0.0078125" x 0.0078125") iron plate shown thus
- 0.00009765625 x 0.00009765625 m (0.00390625" x 0.00390625") iron plate shown thus
- 0.000048828125 x 0.000048828125 m (0.001953125" x 0.001953125") iron plate shown thus
- 0.0000244140625 x 0.0000244140625 m (0.0009765625" x 0.0009765625") iron plate shown thus
- 0.00001220703125 x 0.00001220703125 m (0.00048828125" x 0.00048828125") iron plate shown thus
- 0.000006103515625 x 0.000006103515625 m (0.000244140625" x 0.000244140625") iron plate shown thus
- 0.0000030517578125 x 0.0000030517578125 m (0.0001220703125" x 0.0001220703125") iron plate shown thus
- 0.00000152587890625 x 0.00000152587890625 m (0.00006103515625" x 0.00006103515625") iron plate shown thus
- 0.000000762939453125 x 0.000000762939453125 m (0.000030517578125" x 0.000030517578125") iron plate shown thus
- 0.0000003814697265625 x 0.0000003814697265625 m (0.0000152587890625" x 0.0000152587890625") iron plate shown thus
- 0.00000019073486328125 x 0.00000019073486328125 m (0.00000762939453125" x 0.00000762939453125") iron plate shown thus
- 0.000000095367431640625 x 0.000000095367431640625 m (0.000003814697265625" x 0.000003814697265625") iron plate shown thus
- 0.0000000476837158203125 x 0.0000000476837158203125 m (0.0000019073486328125" x 0.0000019073486328125") iron plate shown thus
- 0.00000002384185791015625 x 0.00000002384185791015625 m (0.00000095367431640625" x 0.00000095367431640625") iron plate shown thus
- 0.000000011920928955078125 x 0.000000011920928955078125 m (0.000000476837158203125" x 0.000000476837158203125") iron plate shown thus
- 0.00000000596046447765625 x 0.00000000596046447765625 m (0.0000002384185791015625" x 0.0000002384185791015625") iron plate shown thus
- 0.000000002980232238828125 x 0.000000002980232238828125 m (0.00000011920928955078125" x 0.00000011920928955078125") iron plate shown thus
- 0.0000000014901161194140625 x 0.0000000014901161194140625 m (0.0000000596046447765625" x 0.0000000596046447765625") iron plate shown thus
- 0.00000000074505805970703125 x 0.00000000074505805970703125 m (0.00000002980232238828125" x 0.00000002980232238828125") iron plate shown thus
- 0.000000000372529029853515625 x 0.000000000372529029853515625 m (0.000000014901161194140625" x 0.000000014901161194140625") iron plate shown thus
- 0.000000000186264514926765625 x 0.000000000186264514926765625 m (0.0000000074505805970703125" x 0.0000000074505805970703125") iron plate shown thus
- 0.00000000009313225746328125 x 0.00000000009313225746328125 m (0.00000000372529029853515625" x 0.00000000372529029853515625") iron plate shown thus
- 0.000000000046566128731640625 x 0.000000000046566128731640625 m (0.00000000186264514926765625" x 0.00000000186264514926765625") iron plate shown thus
- 0.0000000000232830643658203125 x 0.0000000000232830643658203125 m (0.0000000009313225746328125" x 0.0000000009313225746328125") iron plate shown thus
- 0.00000000001164153218291015625 x 0.00000000001164153218291015625 m (0.00000000046566128731640625" x 0.00000000046566128731640625") iron plate shown thus
- 0.00000000000582076609145703125 x 0.00000000000582076609145703125 m (0.000000000232830643658203125" x 0.000000000232830643658203125") iron plate shown thus
- 0.000000000002910383045728515625 x 0.000000000002910383045728515625 m (0.0000000001164153218291015625" x 0.0000000001164153218291015625") iron plate shown thus
- 0.0000000000014551915228642890625 x 0.0000000000014551915228642890625 m (0.0000000000582076609145703125" x 0.0000000000582076609145703125") iron plate shown thus
- 0.00000000000072759576142854453125 x 0.00000000000072759576142854453125 m (0.00000000002910383045728515625" x 0.00000000002910383045728515625") iron plate shown thus
- 0.0000000000003637978807142854453125 x 0.0000000000003637978807142854453125 m (0.000000000014551915228642890625" x 0.000000000014551915228642890625") iron plate shown thus
- 0.000000000000181898940357142854453125 x 0.000000000000181898940357142854453125 m (0.0000000000072759576142854453125" x 0.0000000000072759576142854453125") iron plate shown thus
- 0.000000000000090949470178727265625 x 0.000000000000090949470178727265625 m (0.000000000003637978807142854453125" x 0.000000000003637978807142854453125") iron plate shown thus
- 0.00000000000004547473508936328125 x 0.00000000000004547473508936328125 m (0.00000000000181898940357142854453125" x 0.00000000000181898940357142854453125") iron plate shown thus
- 0.000000000000022737367544681640625 x 0.000000000000022737367544681640625 m (0.00000000000090949470178727265625" x 0.00000000000090949470178727265625") iron plate shown thus
- 0.0000000000000113686837723403203125 x 0.0000000000000113686837723403203125 m (0.0000000000004547473508936328125" x 0.0000000000004547473508936328125") iron plate shown thus
- 0.00000000000000568434188617015625 x 0.00000000000000568434188617015625 m (0.00000000000022737367544681640625" x 0.00000000000022737367544681640625") iron plate shown thus
- 0.000000000000002842170943058528125 x 0.000000000000002842170943058528125 m (0.000000000000113686837723403203125" x 0.000000000000113686837723403203125") iron plate shown thus
- 0.0000000000000014210854715292640625 x 0.0000000000000014210854715292640625 m (0.0000000000000568434188617015625" x 0.0000000000000568434188617015625") iron plate shown thus
- 0.00000000000000071054273576463203125 x 0.00000000000000071054273576463203125 m (0.00000000000002842170943058528125" x 0.00000000000002842170943058528125") iron plate shown thus
- 0.00000000000000035527136788231640625 x 0.00000000000000035527136788231640625 m (0.000000000000014210854715292640625" x 0.000000000000014210854715292640625") iron plate shown thus
- 0.00000000000000017763568394117015625 x 0.00000000000000017763568394117015625 m (0.0000000000000071054273576463203125" x 0.0000000000000071054273576463203125") iron plate shown thus
- 0.00000000000000008881784197058528125 x 0.00000000000000008881784197058528125 m (0.0000000000000035527136788231640625" x 0.0000000000000035527136788231640625") iron plate shown thus
- 0.000000000000000044408920985292640625 x 0.000000000000000044408920985292640625 m (0.0000000000000017763568394117015625" x 0.0000000000000017763568394117015625") iron plate shown thus
- 0.0000000000000000222044604926463203125 x 0.0000000000000000222044604926463203125 m (0.0000000000000008881784197058528125" x 0.0000000000000008881784197058528125") iron plate shown thus
- 0.0000000000000000111022302463231640625 x 0.0000000000000000111022302463231640625 m (0.00000000000000044408920985292640625" x 0.00000000000000044408920985292640625") iron plate shown thus
- 0.000000000000000005551115123162015625 x 0.000000000000000005551115123162015625 m (0.000000000000000222044604926463203125" x 0.000000000000000222044604926463203125") iron plate shown thus
- 0.0000000000000000027755575615610078125 x 0.0000000000000000027755575615610078125 m (0.000000000000000111022302463231640625" x 0.000000000000000111022302463231640625") iron plate shown thus
- 0.00000000000000000138777878078050390625 x 0.00000000000000000138777878078050390625 m (0.00000000000000005551115123162015625" x 0.00000000000000005551115123162015625") iron plate shown thus
- 0.000000000000000000693889390390251953125 x 0.000000000000000000693889390390251953125 m (0.000000000000000027755575615610078125" x 0.000000000000000027755575615610078125") iron plate shown thus
- 0.00000000000000000034694469519512578125 x 0.00000000000000000034694469519512578125 m (0.0000000000000000138777878078050390625" x 0.0000000000000000138777878078050390625") iron plate shown thus
- 0.00000000000000000017347234759757890625 x 0.00000000000000000017347234759757890625 m (0.00000000000000000693889390390251953125" x 0.00000000000000000693889390390251953125") iron plate shown thus
- 0.000000000000000000086736173798789453125 x 0.000000000000000000086736173798789453125 m (0.0000000000000000034694469519512578125" x 0.0000000000000000034694469519512578125") iron plate shown thus
- 0.0000000000000000000433680868987947265625 x 0.0000000000000000000433680868987947265625 m (0.0000000000000000017347234759757890625" x 0.0000000000000000017347234759757890625") iron plate shown thus
- 0.00000000000000000002168404344939736328125 x 0.00000000000000000002168404344939736328125 m (0.00000000000000000086736173798789453125" x 0.00000000000000000086736173798789453125") iron plate shown thus
- 0.000000000000000000010842021724698681640625 x 0.000000000000000000010842021724698681640625 m (0.000000000000000000433680868987947265625" x 0.000000000000000000433680868987947265625") iron plate shown thus
- 0.0000000000000000000054210108648493403203125 x 0.00000000000000000000542

ENBRIDGE LEASE SITE

INDIVIDUAL OWNERSHIP PLAN

REVISION

2



OWNER(S): ENBRIDGE PIPELINES INC.

TITLE No.: 2708832/2

This plan certified correct this
5th day of June, 2014.

David Quirk

David J. Quirk
Manitoba Land Surveyor

**NOTE: NOT TO BE USED FOR
CONSTRUCTION PURPOSES**

LEGEND:


- Survey Monuments found shown thus: ○
 - 0.019 x 0.019 Iron Posts planted shown thus: ●
 - 0.025 x 0.025 Iron Posts planted shown thus: ■
 - Temporary Point shown thus: ⊠
 - Portions referred to shown thus:
 - Temporary Work Space shown thus:
- Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:5000	
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-1		David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
1.	APR. 28, 2014	REDUCED LEASE SIZE BY 20m (WEST SIDE)	SM-0112-13-1		
2.	JUN. 5, 2014	REVISED LANDOWNER & REVISED DRAWING NAME	SM-0112-13-1		
SURVEYED BY: MC		CALC'D BY: CO	DRAWN BY: JB		SM-0112-13-1-IOP-1-R2

ENBRIDGE LEASE SITE INDIVIDUAL OWNERSHIP PLAN

REVISION

2



DETAIL
SCALE - 1:1000

NOTE: NOT TO BE USED FOR CONSTRUCTION PURPOSES


- LEGEND:**
- Survey Monuments found shown thus: ○
 - 0.019 x 0.019 Iron Posts planted shown thus: ●
 - 0.025 x 0.025 Iron Posts planted shown thus: ■
 - Temporary Point shown thus: ⊠
 - Portions referred to shown thus:
 - Temporary Work Space shown thus:
- Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:1000	
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-1		David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
1.	APR. 28, 2014	REDUCED LEASE SIZE BY 20m (WEST SIDE)	SM-0112-13-1		
2.	JUN. 5, 2014	REVISED LANDOWNER & REVISED DRAWING NAME	SM-0112-13-1		
SURVEYED BY: MC		CALC'D BY: CO	DRAWN BY: JB		SM-0112-13-1-IOP-2-R2



INDIVIDUAL OWNERSHIP PLAN

REVISION
2



NE 1/4, Sec 17-9-28 W P M

AREA IN NEW LEASE 'A':	1.81 ha (4.48 ac.)
AREA IN NEW LEASE 'B':	0.10 ha (0.25 ac.)
TOTAL AREA:	1.91 ha (4.73 ac.)

OWNER(S): INTERPROVINCIAL PIPELINE INC.

TITLE No.: 1534951/2

This plan certified correct this
5th day of June, 2014.

David Quirk
David J. Quirk
Manitoba Land Surveyor

**NOTE: NOT TO BE USED FOR
CONSTRUCTION PURPOSES**


LEGEND:

- Survey Monuments found shown thus: ○
 - 0.019 x 0.019 Iron Posts planted shown thus: ●
 - 0.025 x 0.025 Iron Posts planted shown thus: ■
 - Temporary Point shown thus: ⊠
 - Portions referred to shown thus: [Red outline]
 - Temporary Work Space shown thus: [Pink outline]
- Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:5000	David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-2		
1.	APR. 28, 2014	ADDED EXISTING ACCESS ROAD & ADDED LEASE AREA IN THE SW CORNER	SM-0112-13-2		
2.	JUN. 5, 2014	REVISED DETAIL ON PAGE 2 & REVISED DRAWING NAME	SM-0112-13-2		
SURVEYED BY: MC		CALC'D BY: CO	DRAWN BY: JB		SM-0112-13-2-IOP-1-R2



**LEASE SITE
INDIVIDUAL OWNERSHIP PLAN**



NOTE: NOT TO BE USED FOR CONSTRUCTION PURPOSES

LEGEND:

- Survey Monuments found shown thus: ○
 - 0.019 x 0.019 Iron Posts planted shown thus: ●
 - 0.025 x 0.025 Iron Posts planted shown thus: ■
 - Temporary Point shown thus: ⊠
 - Portions referred to shown thus: [Red outline]
 - Temporary Work Space shown thus: [Pink outline]
- Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:2000	David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-2		
1.	APR. 28, 2014	ADDED EXISTING ACCESS ROAD & ADDED LEASE AREA IN THE SW CORNER	SM-0112-13-2		
2.	JUN. 5, 2014	REVISED DETAIL ON PAGE 2 & REVISED DRAWING NAME	SM-0112-13-2		
SURVEYED BY: MC		CALC'D BY: CO	DRAWN BY: JB		SM-0112-13-2-IOP-2-R2




Appendix B
Typical Profile and Cross-Sections
of Pipeline, Road, and Utility Crossings

Drawing Name	Drawing Number
Typical Pipeline Installation	A-PPD-590 SHT. 153 Rev. A
Typical Foreign Pipeline Crossing	A-TYP-590 SHT. 155b Rev. 2
Typical Foreign Cable Crossing	A-TYP-590 SHT. 155c Rev. B

NOMINAL PIPE DIAMETER	MINIMUM DIMENSION 'B' IN EARTH	MINIMUM DIMENSION 'B' IN ROCK	MINIMUM DIMENSION 'A' IN EARTH	MINIMUM DIMENSION 'A' IN ROCK
88.9mm	1.5m	.65m	375mm	375mm
114.3mm	1.5m	.65m	400mm	400mm
168.3mm	1.5m	.65m	450mm	450mm
219.1mm	1.5m	.65m	600mm	600mm
273.1mm	1.5m	.65m	600mm	600mm
323.9mm	1.5m	.65m	600mm	600mm
406.4mm	1.5m	.65m	600mm	600mm

NORMAL PIPE LOCATION UNLESS OTHERWISE SPECIFIED BY COMPANY INSPECTOR OR BY CONTRACT DRAWING	
DIMENSION 'C'	DIMENSION 'D'
TRUNK LINES	8m
GATHERING LINES	8m
TRUNK LINES	10m
GATHERING LINES	10m

20m R.O.W.
15m R.O.W.
13m R.O.W.




SECTION

REV	REVISION DESCRIPTION	BY	DATE	CHKD	APP	ENGINEERING RECORD	
						PROJECT	
						PROJECT No.	
						DATE	1993-12-01
						DESIGNED BY	J.D. MICHEL
						ENGINEER	J.T. ZELAZNY
						LAST UPDATE:	2013-09-23, 09:09
						SCALE	N.T.S.
						ACAD DWG No.	TYP590153.DWG
J:\DWG\TYP						DRAWING No. A-PPD-590	
						SHT. 153	
						REV A	



ENBRIDGE PIPELINES (SASKATCHEWAN) INC.
TYPICAL PIPELINE INSTALLATION
DITCH & PIPE CROSS SECTION



- NOTES: DIMENSIONS IN METERS.
1. TRENCH AT EXISTING ENBRIDGE PIPELINE TO BE EXPOSED BY WATER WASHING OR BY HAND PRIOR TO ANY MECHANICAL EXCAVATION.
 2. IN CASES WHERE EXISTING ENBRIDGE PIPELINE IS AT ABNORMAL DEPTH, THE CABLE CROSSING MAY BE ABOVE IF APPROVED BY ENBRIDGE PIPELINES. 0.6 m MINIMUM CLEARANCE SHALL BE MAINTAINED.
 3. SAND PADDING NOT REQUIRED FOR STEEL PIPELINES. SELECTED FILL MATERIAL MAY BE SUBSTITUTED IF APPROVED BY ENBRIDGE.
 4. ADEQUATE NOTICE SHALL BE GIVEN TO ENBRIDGE SO THAT THEIR REPRESENTATIVE MAY BE PRESENT WHEN CROSSING INSTALLATION IS MADE.

REV	REVISION DESCRIPTION	BY	DATE	CHKD	APP	ENGINEERING RECORD			
B	UPDATED NOTES	JDM	2011-07-26	LM		PROJECT	DATE	DESIGNED BY	SCALE
						AEZ/FILE	1999-07-21	J.D. MICHEL	N.T.S.
						DRAWN BY		DIA. COOK	
						CHKD BY		ENGINEER	
						LAST UPDATE:			
						LAST UPDATE:			
						SCALE			
						N.T.S.			
						TITLE			
						ENBRIDGE PIPELINES (SASKATCHEWAN) INC. TYPICAL FOREIGN CABLE CROSSING CROSS SECTION			
						DRAWING No.	A-TYP-590	SHT.	155c
						REV B			




Appendix C

Pipeline ZML-WV-01 Crossing Plans


Drawing Name	Drawing Number
Enbridge Pipeline Crossing (Xing #1)	SM-0112-13-3-XEB-1-R2
Enbridge Pipeline Crossing (Xing #2)	SM-0112-13-3-XEB-2-R2
Enbridge Pipeline Crossing (Xing #3)	SM-0112-13-3-XEB-3-R2
Enbridge Pipeline Crossing (Xing #5)	SM-0112-13-3-XEB-5-R2
Access Road Crossing (Xing #4)	SM-0112-13-3-XNG-4-R2

DETAIL
SCALE - 1:1000


LOCATION PLAN
SCALE - 1:10000



NW 1/4, Sec 17-9-28 W P M



CROSS-SECTION
HORIZONTAL SCALE - 1:200
VERTICAL SCALE - 1:200



PROFILE
HORIZONTAL SCALE - 1:200
VERTICAL SCALE - 1:200

NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.

PIPE SPECIFICATIONS: ENBRIDGE(SASK)		PIPE SPECIFICATIONS: ENBRIDGE	
Carrier Pipe	CARRIER PIPE	Carrier Pipe	CARRIER PIPE
Outside Diameter:	406.4 mm	Outside Diameter:	914.0 mm
Wall Thickness:	9.5 mm	Wall Thickness:	10.32 mm
Specification / Grade:	CSA Z245.1 G359 CAT. II	Specification / Grade:	X-70
Pipe Material:	Steel	Pipe Material:	Steel
Year of Installation:	2014	Year of Installation:	2008/2009
Type of Joint:	Welded	Type of Joint:	N/A
Protection:	FBE	Protection:	APIELPSL-2FBE
Max. Operating Pressure:	7378 kPa	Max. Operating Pressure:	N/A
Min. Test Pressure:	11067 kPa	Min. Test Pressure:	N/A
Product Conveyed:	Clean Oil	Product Conveyed:	Crude Oil

ENBRIDGE PIPELINES (SASKATCHEWAN) INC.

CROSSING PLAN OF ENBRIDGE PIPELINES INC. PLAN No 51079 BLTO IN THE NW 1/4, Sec. 17, Twp 9, Rge 28, W P M MANITOBA

CERTIFIED CORRECT: *David Quirk* June 5th, 2014

MIDWEST SURVEYS
DAVID J. QUIRK M.L.S.
ESTEVAN - PHONE: 306-634-2635
FAX: 306-634-3164

REVISION **2**




SM-0112-13-3-XEB-1-R2

NO.	DATE	REVISION / ISSUED	JOB NO.
0.	FEB. 20, 2014	PLAN ISSUED	SM-0112-13-3
1.	APR. 28, 2014	REVISED PIPELINE ROUTE & R/W WIDTH	SM-0112-13-3
2.	JUN. 5, 2014	REVISED PIPE SPECIFICATIONS & REVISED DRAWING NAME	SM-0112-13-3

SURVEYED BY: MH/MC CALC'D BY: JB DRAWN BY: JB

DETAIL
SCALE - 1:1000

LOCATION PLAN
SCALE - 1:10000



CROSS-SECTION
HORIZONTAL SCALE - 1:200
VERTICAL SCALE - 1:200

PROFILE
HORIZONTAL SCALE - 1:200
VERTICAL SCALE - 1:200

NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.

PIPE SPECIFICATIONS: ENBRIDGE(SASK)		PIPE SPECIFICATIONS: ENBRIDGE(WESTSPUR)	
Carrier Pipe	406.4 mm	Carrier Pipe	168.3 mm
Outside Diameter	406.4 mm	Outside Diameter	168.3 mm
Wall Thickness	9.5 mm	Wall Thickness	4.8 mm
Specification / Grade	CSA Z245.1 G359 CAT. II	Specification / Grade	CSA Z245.1 G290
Pipe Material	Steel	Pipe Material	Steel (6" ZML-AC-03)
Year of Installation	2014	Year of Installation	2008
Type of Joint	Welded	Type of Joint	Welded
Protection	FBE	Protection	Y/J1
Max. Operating Pressure	7378 kPa	Max. Operating Pressure	9830 kPa
Min. Test Pressure	11067 kPa	Min. Test Pressure	14822 kPa
Product Conveyed	Clean Oil	Product Conveyed	Natural Gas Liquids

CROSSING PLAN OF ENBRIDGE PIPELINES (WESTSPUR) INC. PLAN No 49437 BLTO
IN THE NW 1/4, Sec. 17, Twp 9, Rge 28, W P M
MANITOBA

CERTIFIED CORRECT:
David Quirk
DATE: June 5th, 2014

MIDWEST SURVEYS
DAVID J. QUIRK M.L.S.
ESTEVEN - PHONE: 306-634-2635
FAX: 306-634-3164

REVISION 2

NO.	DATE	REVISION / ISSUED	JOB No.
0.	FEB. 20, 2014	PLAN ISSUED	SM-0112-13-3
1.	APR. 28, 2014	REVISED PIPELINE ROUTE & R/W WIDTH	SM-0112-13-3
2.	JUN. 5, 2014	REVISED PIPE SPECIFICATIONS & REVISED DRAWING NAME	SM-0112-13-3

SURVEYED BY: MH/MC | CALC'D BY: CO | DRAWN BY: JB


SM-0112-13-3-XEB-2-R2

DETAIL
SCALE - 1:1000

PIPE SPECIFICATIONS: ENBRIDGE(WESTSPUR)


Carrier Pipe	406.4 mm
Outside Diameter:	406.4 mm
Wall Thickness:	7.1 mm
Specification / Grade:	API 5LX-52
Pipe Material:	Steel (16" ZML-AC-02)
Year of Installation:	1957
Type of Joint:	Welded
Protection:	CT
Max. Operating Pressure:	7378 kPa
Min. Test Pressure:	N/A
Product Conveyed:	Clean Oil

LOCATION PLAN
SCALE - 1:10000





PIPE SPECIFICATIONS: ENBRIDGE(SASK)

Carrier Pipe	406.4 mm
Outside Diameter:	406.4 mm
Wall Thickness:	9.5 mm
Specification / Grade:	CSA Z245.1 G359 CAT. II
Pipe Material:	Steel
Year of Installation:	2014
Type of Joint:	Welded
Protection:	FBE
Max. Operating Pressure:	7378 kPa
Min. Test Pressure:	11067 kPa
Product Conveyed:	Clean Oil



CROSS-SECTION
HORIZONTAL SCALE - 1:200
VERTICAL SCALE - 1:200

PROFILE
HORIZONTAL SCALE - 1:200
VERTICAL SCALE - 1:200



NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.

PIPE SPECIFICATIONS: ENBRIDGE(SASK)		PIPE SPECIFICATIONS: ENBRIDGE(WESTSPUR)	
CARRIER PIPE	CARRIER PIPE	CARRIER PIPE	CARRIER PIPE
Outside Diameter:	406.4 mm	Outside Diameter:	323.9 mm
Wall Thickness:	9.5 mm	Wall Thickness:	7.1 mm
Specification / Grade:	CSA Z245.1 G359 CAT. II	Specification / Grade:	API 5LX-46
Pipe Material:	Steel	Pipe Material:	Steel (12" ZML-AC-01)
Year of Installation:	2014	Year of Installation:	1956
Type of Joint:	Welded	Type of Joint:	Welded
Protection:	FBE	Protection:	CT
Max. Operating Pressure:	7378 kPa	Max. Operating Pressure:	7380 kPa
Min. Test Pressure:	11067 kPa	Min. Test Pressure:	9652 kPa
Product Conveyed:	Clean Oil	Product Conveyed:	Clean Oil

ENBRIDGE PIPELINES (SASKATCHEWAN) INC.

CROSSING PLAN OF ENBRIDGE PIPELINES (WESTSPUR) INC. PLAN No 785 BLTO
IN THE NW 1/4, Sec. 17, Twp 9, Rge 28, W P M
MANITOBA

CERTIFIED CORRECT: *David Quirk*
DATE: June 5th, 2014

MIDWEST SURVEYS
DAVID J. QUIRK M.L.S.
ESTEVAN - PHONE: 306-634-2635
FAX: 306-634-3164

REVISION **2**

SM-0112-13-3-XEB-3-R2


NO.	DATE	REVISION / ISSUED	JOB NO.
0.	FEB. 20, 2014	PLAN ISSUED	SM-0112-13-3
1.	APR. 28, 2014	REVISED PIPELINE ROUTE & R/W WIDTH	SM-0112-13-3
2.	JUN. 5, 2014	REVISED PIPE SPECIFICATIONS & REVISED DRAWING NAME	SM-0112-13-3

SURVEYED BY: M/M/MC CALC'D BY: CO DRAWN BY: JB


PLAN SHOWING

Typical Access Road Crossing

NE 1/4, Sec 17, Twp 9, Rge 28, W P M



NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.


TYPICAL CROSSING DETAIL

Not to Scale

Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:5000	David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-3		
1.	APR. 28, 2014	REVISED PIPELINE ROUTE, R/W WIDTH & REVISED TEMPORARY WORKSPACE	SM-0112-13-3		
1.	JUN. 5, 2014	REVISED DRAWING NAME	SM-0112-13-3		
SURVEYED BY: MH/MC		CALC'D BY: CO	DRAWN BY: JB		SM-0112-13-3-XNG-4-R2




Appendix D Pipeline ZML-VT-01 Crossing Plans

Drawing Name	Drawing Number
Pipeline Crossing (Xing #1)	SM-0112-13-4-XNG-1-R2
Pipeline Crossing (Xing #2)	SM-0112-13-4-XNG-2-R2
Overhead Hydro Crossing (Xing #3)	SM-0112-13-4-XNG-3-R2
Telephone Cable Crossing (Xing #4)	SM-0112-13-4-XNG-4-R2
Pipeline Crossing (Xing #6)	SM-0112-13-4-XNG-6-R2
Telephone Cable Crossing (Xing #7)	SM-0112-13-4-XNG-7-R2
Overhead Hydro Crossing (Xing #8)	SM-0112-13-4-XNG-8-R2
Overhead Hydro Crossing (Xing #9)	SM-0112-13-4-XNG-9-R2
Buried Cable Crossing (Xing #10)	SM-0112-13-4-XNG-10-R2
Flowline Crossing (Xing #11)	SM-0112-13-4-XNG-11-R2
Telephone Cable Crossing (Xing #12)	SM-0112-13-4-XNG-12-R2
Flowline Crossing (Xing #13)	SM-0112-13-4-XNG-13-R2
Highway Crossing (Xing #5)	SM-0112-13-4-XRD-5-R2


PLAN SHOWING

Typical Pipeline Crossing

NE 1/4, Sec 17, Twp 9, Rge 28, W P M



NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.



TYPICAL CROSSING DETAIL

Not to Scale


Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:5000	David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-4		
1.	APR. 28, 2014	REVISED PIPELINE ROUTE, R/W WIDTH & REVISED TEMPORARY WORKSPACE	SM-0112-13-4		
2.	JUN. 5, 2014	REVISED R/W ROUTE IN NW 1/4, Sec 17 & REVISED DRAWING NAME	SM-0112-13-4		
SURVEYED BY: MH/MC		CALC'D BY: CO	DRAWN BY: JB		SM-0112-13-4-XNG-1-R2


PLAN SHOWING

Typical Pipeline Crossing

NE 1/4, Sec 17, Twp 9, Rge 28, W P M



NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.



TYPICAL CROSSING DETAIL

Not to Scale


Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:5000	David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-4		
1.	APR. 28, 2014	REVISED PIPELINE ROUTE, R/W WIDTH & REVISED TEMPORARY WORKSPACE	SM-0112-13-4		
2.	JUN. 5, 2014	REVISED R/W ROUTE IN NW 1/4, Sec 17 & REVISED DRAWING NAME	SM-0112-13-4		
SURVEYED BY: MH/MC		CALC'D BY: CO	DRAWN BY: JB		SM-0112-13-4-XNG-2-R2


PLAN SHOWING

Typical Overhead Hydroline Crossing

NE 1/4, Sec 17, Twp 9, Rge 28, W P M



NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.




TYPICAL CROSSING DETAIL
Not to Scale


Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:5000	David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-4		
1.	APR. 28, 2014	REVISED PIPELINE ROUTE, R/W WIDTH & REVISED TEMPORARY WORKSPACE	SM-0112-13-4		
2.	JUN. 5, 2014	REVISED R/W ROUTE IN NW 1/4, Sec 17 & REVISED DRAWING NAME	SM-0112-13-4		
SURVEYED BY: MH/MC		CALC'D BY: CO	DRAWN BY: JB		SM-0112-13-4-XNG-3-R2

PLAN SHOWING
 Typical Telephone Cable Crossing
 NW 1/4, Sec 16, Twp 9, Rge 28, W P M



NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.




TYPICAL CROSSING DETAIL
 Not to Scale


Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:5000	David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-4		 SM-0112-13-4-XNG-4-R2
1.	APR. 28, 2014	REVISED TEMPORARY WORKSPACE	SM-0112-13-4		
2.	JUN. 5, 2014	REVISED DRAWING NAME	SM-0112-13-4		
SURVEYED BY: MH/MC		CALC'D BY: CO	DRAWN BY: JB		

PLAN SHOWING
 Typical Pipeline Crossing
 NW 1/4, Sec 16, Twp 9, Rge 28, W P M



NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.




TYPICAL CROSSING DETAIL
 Not to Scale


Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:5000	David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-4		
1.	APR. 28, 2014	REVISED TEMPORARY WORKSPACE	SM-0112-13-4		
2.	JUN. 5, 2014	REVISED DRAWING NAME	SM-0112-13-4		
SURVEYED BY: MH/MC		CALC'D BY: CO	DRAWN BY: JB	SM-0112-13-4-XNG-6-R2	

PLAN SHOWING
 Typical Telephone Cable Crossing
 NW 1/4, Sec 16, Twp 9, Rge 28, W P M



NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.



TYPICAL CROSSING DETAIL
 Not to Scale


Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:5000	David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-4		
1.	APR. 28, 2014	REVISED TEMPORARY WORKSPACE	SM-0112-13-4		
2.	JUN. 5, 2014	REVISED DRAWING NAME	SM-0112-13-4		
SURVEYED BY: MH/MC		CALC'D BY: CO	DRAWN BY: JB		SM-0112-13-4-XNG-7-R2


PLAN SHOWING

Typical Overhead Hydroline Crossing

NW 1/4, Sec 16, Twp 9, Rge 28, W P M



NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.



PROPOSED PIPE

TYPICAL CROSSING DETAIL

Not to Scale


Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:5000	David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-4		
1.	APR. 28, 2014	REVISED TEMPORARY WORKSPACE	SM-0112-13-4		
2.	JUN. 5, 2014	REVISED DRAWING NAME	SM-0112-13-4		
SURVEYED BY: MH/MC		CALC'D BY: CO	DRAWN BY: JB	SM-0112-13-4-XNG-8-R2	


PLAN SHOWING

Typical Overhead Hydroline Crossing

NW 1/4, Sec 16, Twp 9, Rge 28, W P M



NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.



TYPICAL CROSSING DETAIL

Not to Scale


Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:5000	David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-4		
1.	APR. 28, 2014	REVISED TEMPORARY WORKSPACE	SM-0112-13-4		
2.	JUN. 5, 2014	REVISED DRAWING NAME	SM-0112-13-4		
SURVEYED BY: MH/MC		CALC'D BY: CO	DRAWN BY: JB		
					SM-0112-13-4-XNG-9-R2


PLAN SHOWING

Typical Buried Hydro Cable Crossing

NW 1/4, Sec 16, Twp 9, Rge 28, W P M



NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.




TYPICAL CROSSING DETAIL

Not to Scale


Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:5000	MIDWEST SURVEYS INC.
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-4		130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
1.	APR. 28, 2014	REVISED TEMPORARY WORKSPACE	SM-0112-13-4		
2.	JUN. 5, 2014	REVISED DRAWING NAME	SM-0112-13-4		
SURVEYED BY: MH/MC		CALC'D BY: CO	DRAWN BY: JB		SM-0112-13-4-XNG-10-R2

PLAN SHOWING
 Typical Flowline Crossing
 NW 1/4, Sec 16, Twp 9, Rge 28, W P M



NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.



TYPICAL CROSSING DETAIL
 Not to Scale


Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:5000	David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-4		
1.	APR. 28, 2014	REVISED TEMPORARY WORKSPACE	SM-0112-13-4		
2.	JUN. 5, 2014	REVISED DRAWING NAME	SM-0112-13-4		
SURVEYED BY: MH/MC		CALC'D BY: CO	DRAWN BY: JB		SM-0112-13-4-XNG-11-R2


PLAN SHOWING

Typical Telephone Cable Crossing

NW 1/4, Sec 16, Twp 9, Rge 28, W P M



NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.




TYPICAL CROSSING DETAIL

Not to Scale


Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:5000	David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-4		
1.	APR. 28, 2014	REVISED TEMPORARY WORKSPACE	SM-0112-13-4		
2.	JUN. 5, 2014	REVISED DRAWING NAME	SM-0112-13-4		
SURVEYED BY: MH/MC		CALC'D BY: CO	DRAWN BY: JB		SM-0112-13-4-XNG-12-R2

PLAN SHOWING
Typical Flowline Crossing
 NW 1/4, Sec 16, Twp 9, Rge 28, W P M



NOTE: Positions of buried facilities shown are derived from interpretations of signals from electronic devices. Reception of electronic signals is subject to interference and has limitations, therefore it should not be assumed that all buried facilities are shown, and facilities which are shown should not be construed as "located" until physically exposed. All underground installations should be marked by the respective authorities prior to excavation or construction.



TYPICAL CROSSING DETAIL
 Not to Scale

Distances are in metres and decimals thereof.

No.	DATE	REVISION / ISSUED	JOB No.	SCALE 1:5000	David J. Quirk M.L.S. 130 King Street Estevan, SK S4A 2T5 Tel: 306-634-2635
0.	FEB. 18, 2014	PLAN ISSUED	SM-0112-13-4		
1.	APR. 28, 2014	REVISED TEMPORARY WORKSPACE	SM-0112-13-4		
2.	JUN. 5, 2014	REVISED DRAWING NAME	SM-0112-13-4		
SURVEYED BY: MH/MC		CALC'D BY: CO	DRAWN BY: JB	SM-0112-13-4-XNG-13-R2	



Enbridge Pipelines (Saskatchewan) Inc.
Proposed Manitoba Interconnect Project – CC 13 06

Appendix E

Manitoba Interconnect Project Site Breakdown

Drawing Name	Drawing Number
Company Demarcation / Site Breakdown	D-PFD-421 SHT. 1




Appendix F

Westspur Interconnect Facility Drawings

Drawing Name	Drawing Number
14-17-09-28 WPM Plot Plan	D-MIW-410 SHT. 1
16" Mainline Take Off P&ID (Line 23A)	D-MIW-420 SHT. 1
12" Mainline Take Off P&ID (Line 23B)	D-MIW-420 SHT. 2
16" Outgoing Sending Trap Area P&ID (ZML-WV-01)	D-MIW-420 SHT. 3

N. 0+40.000
 N. 0+30.000
 N. 0+20.000
 N. 0+10.000
 N. 0+00.000
 S. 0+10.000
 S. 0+20.000
 S. 0+30.000
 S. 0+40.000
 S. 0+50.000
 S. 0+60.000
 S. 0+70.000
 S. 0+80.000
 S. 0+90.000
 S. 0+100.000
 S. 0+110.000
 S. 0+120.000
 S. 0+130.000
 S. 0+140.000
 S. 0+150.000
 S. 0+160.000
 S. 0+170.000
 S. 0+180.000
 S. 0+190.000
 S. 0+200.000
 S. 0+210.000
 S. 0+220.000
 S. 0+230.000
 S. 0+240.000
 S. 0+250.000
 S. 0+260.000
 S. 0+270.000
 S. 0+280.000
 S. 0+290.000
 S. 0+300.000
 S. 0+310.000
 S. 0+320.000
 S. 0+330.000
 S. 0+340.000
 S. 0+350.000
 S. 0+360.000
 S. 0+370.000
 S. 0+380.000
 S. 0+390.000
 S. 0+400.000
 S. 0+410.000
 S. 0+420.000
 S. 0+430.000
 S. 0+440.000
 S. 0+450.000
 S. 0+460.000
 S. 0+470.000
 S. 0+480.000
 S. 0+490.000
 S. 0+500.000
 S. 0+510.000
 S. 0+520.000
 S. 0+530.000
 S. 0+540.000
 S. 0+550.000
 S. 0+560.000
 S. 0+570.000
 S. 0+580.000
 S. 0+590.000
 S. 0+600.000
 S. 0+610.000
 S. 0+620.000
 S. 0+630.000
 S. 0+640.000
 S. 0+650.000
 S. 0+660.000
 S. 0+670.000
 S. 0+680.000
 S. 0+690.000
 S. 0+700.000
 S. 0+710.000
 S. 0+720.000
 S. 0+730.000
 S. 0+740.000
 S. 0+750.000
 S. 0+760.000
 S. 0+770.000
 S. 0+780.000
 S. 0+790.000
 S. 0+800.000
 S. 0+810.000
 S. 0+820.000
 S. 0+830.000
 S. 0+840.000
 S. 0+850.000
 S. 0+860.000
 S. 0+870.000
 S. 0+880.000
 S. 0+890.000
 S. 0+900.000
 S. 0+910.000
 S. 0+920.000
 S. 0+930.000
 S. 0+940.000
 S. 0+950.000
 S. 0+960.000
 S. 0+970.000
 S. 0+980.000
 S. 0+990.000
 S. 0+1000.000



LEGEND

- 1 RIG LAUNCHER PL-1601
- 2 RIG WORKING AREA
- 3 VALVE ACCESS PLATFORMS
- 4 CORROSION METER
- 5 VALVE ACCESS PLATFORMS
- 6 VALVE ACCESS PLATFORMS
- 7 ESB BUILDING
- 8 ACCESS PLATFORM
- 9 BASKET STRAINER BS-001
- 10 BASKET STRAINER BS-002
- 11 ACCESS PLATFORM
- 12 MANTOSA HYBRID ELECTRICAL SERVICE CABINET (HES)

HOLD
 LOCAL PLANT CO-ORD'S
 N: 0.00
 E: 0.00
 UTM (ZONE 13)
 N: 5,517,653,768
 E: 771,092,581
 UTM (ZONE 14)
 N: 5,517,653,768
 E: 338,936,769

1:300 mm
 0 10000 20000 30000
 0 20 40 60 80
 ENBRIDGE PIPELINE PLAN NO. 49437
 ENBRIDGE PIPELINE PLAN NO. 755
 15288



WESTSPUR INTERCONNECT FACILITY
 14-17-09-28 WPM
 PLOT PLAN

DRAWING No.	REFERENCE DRAWINGS	REV	REVISION DESCRIPTION	BY	DATE	CHKD	APP	ENGINEER'S STAMP	ENGINEERING RECORD
		G	ISSUED FOR BID (GENUS 100-02-02)	MPH	2013-06-20	CJE	-		PROJECT: MANTOSA INTERCONNECT FILE No. CC 13 06
		B	RE-ISSUED FOR REVIEW (GENUS 100-02-02)	AR	2013-12-16	-	-		DATE: 2010-07-23
		C	ISSUED FOR HAZOP (GENUS 100-02-02)	AR	2013-12-20	-	-		DESIGNED BY: C. MCGASKILL
		D	RE-ISSUED FOR HAZOP (GENUS 100-02-02)	AR	2014-01-17	-	-		ENGINEER: 2014-06-23, 15:56
		E	RE-ISSUED FOR REGULATORY (GENUS 100-02-02)	AR	2014-03-25	-	-		SCALE: 1:300
		F	RE-ISSUED FOR REGULATORY (GENUS 100-02-02)	HK	2014-06-05	-	-		DRAWING No. D-MW-410
									SHEET: 1


PROJECT: MANTOSA INTERCONNECT
 FILE No. CC 13 06
 DATE: 2010-07-23
 DESIGNED BY: C. MCGASKILL
 ENGINEER: 2014-06-23, 15:56
 SCALE: 1:300
 DRAWING No. D-MW-410
 SHEET: 1

PROJECT: MANTOSA INTERCONNECT
 FILE No. CC 13 06
 DATE: 2010-07-23
 DESIGNED BY: C. MCGASKILL
 ENGINEER: 2014-06-23, 15:56
 SCALE: 1:300
 DRAWING No. D-MW-410
 SHEET: 1

PROJECT: MANTOSA INTERCONNECT
 FILE No. CC 13 06
 DATE: 2010-07-23
 DESIGNED BY: C. MCGASKILL
 ENGINEER: 2014-06-23, 15:56
 SCALE: 1:300
 DRAWING No. D-MW-410
 SHEET: 1

BS-001
 BASIN OF WILMSON
 MAKE SURE FLOW
 MODEL: C0001-000# RF
 SIZE/PART: 1000# RF
 2.8675CR

FE-01401
 DESIGN WATER
 MAKE SURE FLOW
 MODEL: C0001-000# RF
 SIZE/PART: 1000# RF
 2.8675CR




- NOTES:
1. EXACT THE POINT LOCATION TO BE CONSTRUCTION.
 2. ALL INSTRUMENTATION TAG NUMBERS SHALL BE PREFIXED BY "MM-".
 3. ALL INSTRUMENTATION TAG NUMBERS SHALL BE PREFIXED BY "MM-".
 4. STATE MIXER TO BE INSTALLED WITHIN 0.3-4 PIPE DIAMETER UPSTREAM OF SAMPLE PROBE AND MANUAL SAMPLER.
 5. DO NOT INSTALL AMBIENT COOLING COILS ON THE TOP OF PIPE.
 6. INSTRUMENTATION SHALL BE INSTALLED FOR NORMAL OPERATION. A PLUG SHALL BE ALLOW ADEQUATE SPOOL FOR FUTURE BU-001.
 7. SAMPLE BUILDING AND MM-001 STATIC MIXER.

DRAWING No.	REFERENCE DRAWINGS	REV	REVISION DESCRIPTION	BY	DATE	CHKD	APP	ENGINEER'S STAMP	ENGINEERING RECORD
		0	ISSUED FOR INFORMATION ONLY		07/14/06				PROJECT: MANITOBA INTERCONNECT FILE No. CC 13 06 A/E No. WA1410-03172 DRAWN BY: N. RAMANESH 2013-12-20 CHECKED BY: A. NUYNH 2013-06-17; 11:27 ENGINEER: D. LIM MM42001.DWG N.T.S.
TITLE: WESTSPUR INTERCONNECT FACILITY 16" MAINLINE TAKE OFF PROCESS & INSTRUMENTATION DIAGRAM									
DRAWING No. D-MW-420 SHEET 01 OF 01									

BS-002
 BASIC SURE FLOW
 METER
 MODEL: C0008 RF
 SIZE/RATING: 600# RF
 2.8875SR

FE-91402
 DENSITY METER
 MODEL: C0008 RF
 METER: C0008 RF
 SIZE/RATING: 20 gal/min



- NOTES:
1. EXACT TAKE-OFF LOCATION TBD BY CONSTRUCTION.
 2. EXACT TAKE-OFF EQUIPMENT TAG NUMBERS SHALL BE PREPARED BY "MIM".
 3. ALL SHOWN TO GO FROM NEW ESB TO EFSI VIA CROMER.
 4. STATIC MARKER TO BE INSTALLED WITHIN 0.5-4 PIPE DIAMETERS UPSTREAM OF SAMPLE PROBE AND MANUAL SAMPLER.
 5. DO NOT INSTALL IF AMBIENT -0°C.
 6. ALL INSTRUMENTATIONS SHALL BE INSTALLED ON THE TOP OF PIPE.
 7. INSULATED FOR NORMAL OPERATION. A PLUG SHALL BE INSTALLED FOR FUTURE BU-002.
 8. ALLOW ADEQUATE SPOOL FOR FUTURE BU-002. SAMPLE BUILDING AND MA-002 STATIC METER.

DRAWING No.	REFERENCE DRAWINGS	REV	REVISION DESCRIPTION	BY	DATE	CHKD	APP	ENGINEER'S STAMP	ENGINEERING RECORD
D-MW-420-01		0	ISSUED FOR INFORMATION ONLY		14-06-06				PROJECT: MANITOBA INTERCONNECT FILE No. CC 13 06 DATE: 2013-12-20 DESIGNED BY: N. RAMANESH CHECKED BY: A. HUYNH ENGINEER: D. LIM MIM/2002.DWG
D-MW-420-02									
D-MW-420-03									
D-MW-420-04									
D-MW-420-05									
D-MW-420-06									
D-MW-420-07									
D-MW-420-08									
D-MW-420-09									
D-MW-420-10									
D-MW-420-11									
D-MW-420-12									
D-MW-420-13									
D-MW-420-14									
D-MW-420-15									
D-MW-420-16									
D-MW-420-17									
D-MW-420-18									
D-MW-420-19									
D-MW-420-20									
D-MW-420-21									
D-MW-420-22									
D-MW-420-23									
D-MW-420-24									
D-MW-420-25									
D-MW-420-26									
D-MW-420-27									
D-MW-420-28									
D-MW-420-29									
D-MW-420-30									
D-MW-420-31									
D-MW-420-32									
D-MW-420-33									
D-MW-420-34									
D-MW-420-35									
D-MW-420-36									
D-MW-420-37									
D-MW-420-38									
D-MW-420-39									
D-MW-420-40									
D-MW-420-41									
D-MW-420-42									
D-MW-420-43									
D-MW-420-44									
D-MW-420-45									
D-MW-420-46									
D-MW-420-47									
D-MW-420-48									
D-MW-420-49									
D-MW-420-50									



WESTSPUR INTERCONNECT FACILITY
 12" MAINLINE TAKE-OFF
 PROCESS & INSTRUMENTATION DIAGRAM

DRAWING No. D-MW-420 SHEET 02 REV O




Appendix G

Bakken Metering Line 26 Receiving Trap Site Drawings

Drawing Name	Drawing Number
9-17-9-28 WPM Plot Plan	D-CBK-410 SHT. 1
Incoming Trap Area P&ID (demolition)	D-CBK-420 SHT.1D
Incoming Trap Area P&ID (installation)	D-CBK-420 SHT.1

PR-1601
RECEIVING SCREENER TRAP
DRAWN BY: D. LHM
DESIGNED BY: G. MCCASKILL
DATE: 14-08-06

BS-1004
BASKET STRAINER



- NOTES:
1. HIGH PRESSURE SHUTDOWN OF STEELMAN BAKKEN PUMPS.
 2. EXACT INSTALLATION LOCATION TO BE DETERMINED BY CONSTRUCTION.
 3. INSTRUMENTATION EQUIPMENT TAG NUMBERS SHALL BE PREPARED BY "CRK-".
 4. DO NOT INSTALL IF AMBIENT < 0°C.

DRAWING No.	REFERENCE DRAWINGS	REVISION DESCRIPTION	BY	DATE	CHKD	APP	ENGINEER'S STAMP	ENGINEERING RECORD
0		ISSUED FOR INFORMATION ONLY		14-08-06				PROJECT: MANITOBA INTERCONNECT FILE No: CC 13 06 DATE: 2013-11-28 DESIGNED BY: N. RAMANESH CHECKED BY: A. NUYNH ENGINEER: D. LHM SCALE: N.T.S. DRAWING No: D-CBK-420 SHEET: 01D
TITLE								BAKKEN METERING FACILITY INCOMING TRAP AREA PROCESS & INSTRUMENTATION DIAGRAM
G:\DRAWING\100 ENBRIDGE\100-02 CROMER TUNNAGE\10000 DRAFTING\420 PROCESS AND MECHANICAL FLOW SHEETS (PID)								




Appendix H Manitoba Interconnect Facility Drawings

Drawing Name	Drawing Number
Manitoba Interconnect Facility Plot Plan	D-MIC-410 SHT. 1
Incoming Trap Area P&ID	D-MIC-420 SHT. 1
Sampling / Metering Skid #1 P&ID	D-MIC-420 SHT. 2
Meter Prover Area P&ID	D-MIC-420 SHT. 4
Outgoing Trap Area P&ID	D-MIC-420 SHT. 5
16" Sample Building BU-101	D-MIC-420 SHT. 6
Relief Tank 1	D-MIC-420 SHT. 8

LEGEND

- 1 PIG RECEIVER PR-1801
- 2 PIG RECEIVER WORKING AREA
- 3 VALVE ACCESS PLATFORM
- 4 VALVE ACCESS PLATFORM
- 5 SAMPLE BUILDING BU-101
- 6 METERING SKID-MIC
- 7 MP-900 / PROVER SKID-MIC
- 8 PROVER WORKING AREA
- 9 PIG LAUNCHER WORKING AREA
- 10 PIG LAUNCHER PL-1201
- 11 NEW ESB BLDG
- 12 LAB BLDG
- 13 NOT USED
- 14 RELIEF TANK TK-001
- 15 ENVRD BOX (TRUCK CONN)
- 16 TANK STAR / PLATFORM
- 17 TANK ACCESS STAIRS
- 18 3.3 METER HIGH BRIDGE
- 19 TANK CONTAINMENT
- 20 MANITOBA HYDRO METER CABINET (CSTE)



HOLD
 LOCAL PLANT CC-ORD'S
 N: 0.00
 E: 0.00
 UTM (ZONE 13)
 N: 5,513,653,458
 E: 771,092,581
 UTM (ZONE 14)
 N: 5,513,653,458
 E: 338,936,789


DRAWING No.	REFERENCE DRAWINGS	REV	REVISION DESCRIPTION	BY	DATE	CHKD	APP	ENGINEER'S STAMP	ENGINEERING RECORD
		G	ISSUED FOR BID (GENUS 100-02-02)	CJE	2014-06-20	CJE	-	PROJECT: MANITOBA INTERCONNECT FILE No: CC 13 06	PROJECT: MANITOBA INTERCONNECT FILE No: CC 13 06
		B	RE-ISSUED FOR REVIEW (GENUS 100-02-02)	AR	2013-12-16	-	-	DRAWN BY: J.D. MICHEL CHKD BY: C. REPCHEIN	DATE: 2014-01-17 REVISION: 1
		C	ISSUED FOR HAZOP (GENUS 100-02-02)	AR	2013-12-20	-	-	ENGINEER: J.D. MICHEL	SCALE: 1:300
		D	RE-ISSUED FOR HAZOP (GENUS 100-02-02)	AR	2014-01-17	-	-	ACAD DWG No: MIC41001.dwg	SHR: 01
		E	ISSUED FOR INFORMATION ONLY (GENUS 100-02-02)	AR	2014-02-13	-	-		REV: G
		F	ISSUED FOR REGULATORY (GENUS 100-02-02)	GR	2014-02-20	-	-		



MANITOBA INTERCONNECT CUSTODY TRANSFER
 9-17-9-28 W1M
 PLOT PLAN

DRAWING No. D-MIC-410
 SHEET 01

G:\drafting\100 Enbridge\100-02 Cromer\Tundra Tipka\300 Drafting\410 Facility Plot and Grading Plans (Plot Plan)\MIC41001.dwg



- NOTES:
1. EXACT LOCATION TO BE DETERMINED BY CONSTRUCTION.
 2. INSTRUMENTATION & EQUIPMENT TAG NUMBERS SHALL BE PREPARED BY MIC.
 3. INSTRUMENTATION & EQUIPMENT TAG NUMBERS SHALL BE PREPARED BY MIC.
 4. DO NOT INSTALL IF AMBIENT -50°C.
 5. IF THE CONNECTION SHALL BE INSTALLED ON THE TOP OF PIPE.
 6. P'S ARE NOT PERMANENTLY INSTALLED BUT SHOWN FOR OPERATION.

DRAWING NO.	REFERENCE DRAWINGS	REV	REVISION DESCRIPTION	BY	DATE	CHKD	APP	ENGINEER'S STAMP	ENGINEERING RECORD
G:\DRAWING\100 ENBRIDGE\100-02 CROMER\100-02-02 CROMER TUNDRA\100-02-02 CROMER DRAFTING\420 PROCESS AND MECHANICAL FLOW SHEETS (PID)		0	ISSUED FOR CONSTRUCTION (REVISED 10/12/04)		10/14/06-06				PROJECT: MANITOBA INTERCONNECT FILE NO: WVA140-03172 CC 13 06
									TITLE: MANITOBA INTERCONNECT CUSTODY TRANSFER SAMPLING/METERING SKID #1 PROCESS & INSTRUMENTATION DIAGRAM
									DRAWN BY: N.RADMANESH DATE: 2013-11-28 CHECKED BY: A. NUDNAN DESIGNED BY: C. MCCASKILL SCALE: 2014-06-11, 1:3-42
									ADDD DWG NO: MIC42002.DWG SCALE: N.T.S.
									DRAWING NO: D-MIC-420
									SHT. 02
									REV 0




REV	DATE	DESCRIPTION	DRN	DTG	APPD
01	02/20/12	1ST ISSUE	DJ	PH	SR
02	03/19/12	REVISED	DJ	PH	SR
03	06/20/12	DESIGN CHANGE	DJ	PH	SR
04	06/29/12	IFC	DJ	PH	SR

DE-503 DENSITOMETER
 MODEL: F1000 C AD C
 CALIBRATED TO API GRAVITY

HPU-511 AUTO SAMPLER
 MOTOR: 0.5 HP 3/60/480

ICP-500 INSTRUMENT CIRCULATION PUMP
 MAKE: VEINING
 MODEL: SON8716-H082-32

16"-MIC-420-02
 16" BBLZ1-00-107
 16" BBLZ1-XX-148-25F
 16" BBLZ1-XX-150-25F



DRAWING IS A COPY OF CAMERON REFERENCE DRAWINGS

- CONSTRUCTION NOTES:
1. SHELTER VENDOR'S SCOPE IS LIMITED TO THE BUILDING AND THE ELECTRICAL HEAT TRACING AND PIPE INSULATION.
 2. MANUAL SAMPLER (SWAGelok)
 3. SAMPLE LINES TO SLOPE DOWN MINIMUM 4% TO DISCHARGE AT THIRD OF MAIN HEADER, THE ONE
 4. DESIGN/TESTER MOUNTED
 5. ALL FITTINGS "SWAGelok" SS.
 6. MOV C/W INDICATOR
 7. WITHIN 0.25" PIPE DIAMETERS
 8. UPSTREAM OF SAMPLER PROBE
 9. MANUAL SAMPLER OR OTHERS.
 10. LEAK DETECTION FOR FSU 527B.


DRAWING No.	REFERENCE DRAWINGS	REV	REVISION DESCRIPTION	BY	DATE	CHKD	APP	ENGINEER'S STAMP	ENGINEERING RECORD
SK-2890932 SHT 01	CAMERON BLDG VENDOR DWG	0	ISSUED FOR CONSTRUCTION (REVISED)	PH	2014-06-06				PROJECT: MANITOBA INTERCONNECT FILE No: WVA1410-03172 CC 13 06
SK-2890933 SHT 02	CAMERON BLDG VENDOR DWG								TITLE: MANITOBA INTERCONNECT CUSTODY TRANSFER 16" SAMPLE BUILDING BU-101 PROCESS & INSTRUMENTATION DIAGRAM
CA-DRAFTING\100-ENBRIDGE\100-02-CROMER TUMPA	TECHN 5000 DRAFTING\420 PROCESS AND MECHANICAL FLOW SHEETS (PHD)								SCALE: AS SHOWN SCALE: MIC42006.DWG SCALE: N.T.S.
									DRAWING No. D-MIC-420 SHT. 06 REV. 0



Enbridge Pipelines (Saskatchewan) Inc.
Proposed Manitoba Interconnect Project – CC 13 06

Appendix I Tundra Delivery Facility Drawings


Drawing Name	Drawing Number
12-16-09-28 W1M Plot Plan	D-MIT-410 SHT. 1
Incoming Trap Area	D-MIT-420 SHT. 1



LEGEND

- ① PIG WORKING AREA
- ② PIG RECEIVER PL-1201
- ③ CORROSIUS FE-91201
- ④ ASHER PIGS (EXISTING)
- ⑤ EXISTING TUNDRA PIPERACK
- ⑥ ENBRIDGE ESB BUILDING

HOLD
 LOCAL PLANT CO-ORDS
 N: 0.00
 E: 0.00
 UTM (ZONE 13)
 N: 771,692,281
 E: 338,935,769
 UTM (ZONE 14)
 N: 771,692,281
 E: 338,935,769



DRAWING No.	REFERENCE DRAWINGS	REV	REVISION DESCRIPTION	BY	DATE	CHKD	APP	ENGINEER'S STAMP	ENGINEERING RECORD
		A	ISSUED FOR REVIEW (GENUS 100-02-02)	AR	2013-11-21	-	-		PROJECT: MANITOBA INTERCONNECT FILE No. CC-13.06 WFLR ID: 03172 DESIGNED BY: J.D. MICHEL 2014-01-17 CHKD BY: G. REPCHIN ENGINEER: - LAST UPDATE: 2014-07-02, 10:46 SOLE: 1:200 ACAD DWG No. MIT41001.dwg
		B	RE-ISSUED FOR REVIEW (GENUS 100-02-02)	AR	2013-12-16	-	-		
		C	ISSUED FOR HAZOP (GENUS 100-02-02)	AR	2013-12-20	-	-		
		D	ISSUED FOR REGULATORY (GENUS 100-02-02)	GR	2014-02-21	-	-		



TUNDRA DELIVERY FACILITY
 12-16-09-28 W1M
 PLOT PLAN

