

July 3, 2025

Client File No.: 1069.10

Our File Nos.: S-1315, EMS 020-17-08-11-00

020-17-08-11-0N

T. | Tél.: 204-986-7550

F. | Fax: 204-224-0032

winnipeg.ca

Environment and Climate Change Environmental Stewardship Division Environmental Compliance and Enforcement Box 36 14 Fultz Blvd Winnipeg, MB R3Y 0L6

Attention: Agnes Wittmann, Director

#### RE: NOTICE OF ALTERATION REQUEST FOR SEWPCC

The Water and Waste Department is requesting an alteration to the SEWPCC licence EAL No. 2716 RR to replace the existing Fort Garry St. Vital wastewater siphon river crossing under the Red River.

Please see the attached NOA forms and NOA detailed report to support this request.

Should you have any questions on this NOA request, please contact Ryan Lucky at 204-986-2538 or by email at <a href="mailto:ryanlucky@winnipeg.ca">ryanlucky@winnipeg.ca</a>.

Sincerely,



Cynthia Wiebe, P. Eng., CAMP Manager of Engineering Services Division

#### Attachment

#### RL/dr

- c: Siobhan Burland Ross, M. Eng., P. Eng., Manitoba Conservation and Climate (email)
  Neil Rentz, MSc, Manitoba Conservation and Climate (email)
  - T. W. Shanks, M. Eng., P. Eng., Water and Waste Department (email)
  - C. W. Carroll, P. Eng., Water and Waste Department (email)
  - R. Grosselle, Water and Waste Department (email)
  - S. Cournoyer, P. Eng., Water and Waste Department (email)
  - R. Lucky, P. Eng., Water and Waste Department (email)

#### **Notice of Alteration Form**



File No.: 1069.10	Environmen	nt Act Licence No. : 2716RR
Legal name of the Licensee: City	of Winnipeg	
Name of the development: Sou	th End Pollution C	ontrol Centre
Category and Type of development	per Classes of Develo	pment Regulation:
Waste Treatment and Storage		Wastewater treatment plants
Licensee Contact Person: Stacy Mailing address of the Licensee: 1 City: Winnipeg Phone Number:(204) 986-2142	10-1199 Pacific Ave Province: N	Manitoba Postal Code: R3E 3S8 Email: scournoyer@winnipeg.ca
Name of proponent contact persor Mike Gaudreau, P. Eng.	n for purposes of the er	nvironmental assessment (e.g. consultant):
Phone: (204) 479-6762 Fax:	Mailing addr	ress: 99 Commerce Drive, Winnipeg, MB R3P 0Y7
Email address: Mike.Gaudreau@		
Short Description of Alteration <i>(ma</i> Fort Garry St Vital River Crossin	•	
Alteration fee attached: Yes: The state of t	No: ✓ nt of pipeline with no o	change to environmental effects
Date: 2025-07-03	Signature:	
	Printed name: Stac	y Cournoyer, P. Eng.
A complete Notice of Alteration (I consists of the following componed Cover letter  Notice of Alteration Form  1 electronic copy of the Nove (see "Information Bulletin Developments with Environment Act Licen  \$500 Application fee, if appayable to the Minister of I	A detailed report Alteration to  ces")  pplicable (Cheque, Finance)	Submit the complete NoA to: Director, Environmental Approvals Branch Environment and Climate Change Box 35, 14 Fultz Blvd Winnipeg MB R3Y 0L6 EABDirector@gov.mb.ca For more information: Toll-Free: 1-800-282-8069 Phone: 204-945-8321 Fax: 204-945-5229 https://www.gov.mb.ca/sd/ permits licenses approvals/eal/ licence/ index.html
Note: Per Section 14(3) of the	Environment Act, M	ajor Notices of Alteration must be filed through

submission of an Environment Act Proposal Form (see "Information Bulletin – Environment Act Proposal Report Guidelines")

March 2024 NOA B-02



# Replacement of the Fort Garry-St. Vital Siphon – Notice of Alteration Revision 1

City of Winnipeg

60728226

July 2025



**AECOM Canada ULC** 99 Commerce Drive Winnipeg, MB R3P 0Y7 Canada

T: 204.477.5381 F: 431 800 1210 www.aecom.com

VIA EMAIL (ryanlucky@winnipeg.ca)

Mr. Ryan Lucky Design and Specification Engineer **Engineering Services** Water and Waste

110-1199 Pacific Avenue

Winnipeg, MB R3E 3S8

July 3, 2025

Project #

60728226

Subject: Replacement of the Fort Garry-St. Vital Siphon – Notice of Alteration Revision 1

Dear Mr. Lucky:

We respectfully submit this detailed report supporting the City of Winnipeg's (City's) Notice of Alteration (NoA) to the Environment Act Licence No. 2716 RR (Licence) for the construction of the replacement Fort Garry-St. Vital (FGSV) Wastewater Siphon Crossings of the Red River.

The existing 700 mm and 800 mm high density polyethylene (HDPE) wastewater siphon crossings were located between the eastbound and westbound Fort Garry Bridges on the bottom of the Red River. The siphon crossings of the Red River failed in late 2023 and were isolated from the sewer system in February of 2024, effectively isolating any wastewater from leaking into the Red River.

An emergency bypass has been in operation since February 2024. The emergency bypass consists of two (2) 400 mm HDPE force mains connecting the temporary pumping arrangement at the D'Arcy Lift Station site on the west side of the Red River to the St. Vital Trunk on the east side of the Red River via the eastbound Fort Garry Bridge. The current configuration is able to by-pass the same amount of wastewater as the system prior to failure at an approximate pumping capacity of 820 l/s.

The new FGSV Wastewater Siphon is designed to be hydraulically equivalent to the original crossing of the Red River and will be located south of eastbound Abinojii Mikanah. The new crossing will consist of two (2) new 900 mm HDPE lines, encased and grouted within a 2100 mm reinforced concrete pipe (RCP) installed via microtunnel boring machine (MTBM) within the underlying bedrock crossing the Red River.


We expect the environmental and human health effects resulting from the construction of the replacement FGSV Wastewater Siphon Crossings of the Red River to be insignificant and as such be considered as a minor alteration per Section 14 of The Environment Act.

Sincerely,

**AECOM Canada ULC** 



Mike Gaudreau, P.Eng. Municipal Engineer Conveyance, Water EC/MG/pab Encl.



#### Statement of Qualifications and Limitations

The attached Report (the "Report") has been prepared by AECOM Canada ULC ("AECOM") for the benefit of the Client ("Client") in accordance with the agreement between AECOM and Client, including the scope of work detailed therein (the "Agreement").

The information, data, recommendations and conclusions contained in the Report (collectively, the "Information"):

- is subject to the scope, schedule, and other constraints and limitations in the Agreement and the qualifications contained in the Report (the "Limitations");
- represents AECOM's professional judgement in light of the Limitations and industry standards for the preparation of similar reports;
- may be based on information provided to AECOM which has not been independently verified;
- has not been updated since the date of issuance of the Report and its accuracy is limited to the time period and circumstances in which it was collected, processed, made or issued;
- must be read as a whole and sections thereof should not be read out of such context:
- was prepared for the specific purposes described in the Report and the Agreement; and
- in the case of subsurface, environmental or geotechnical conditions, may be based on limited testing and on the assumption that such conditions are uniform and not variable either geographically or over time.

AECOM shall be entitled to rely upon the accuracy and completeness of information that was provided to it and has no obligation to update such information. AECOM accepts no responsibility for any events or circumstances that may have occurred since the date on which the Report was prepared and, in the case of subsurface, environmental or geotechnical conditions, is not responsible for any variability in such conditions, geographically or over time.

AECOM agrees that the Report represents its professional judgement as described above and that the Information has been prepared for the specific purpose and use described in the Report and the Agreement, but AECOM makes no other representations, or any guarantees or warranties whatsoever, whether express or implied, with respect to the Report, the Information or any part thereof.

Without in any way limiting the generality of the foregoing, any estimates or opinions regarding probable construction costs or construction schedule provided by AECOM represent AECOM's professional judgement in light of its experience and the knowledge and information available to it at the time of preparation. Since AECOM has no control over market or economic conditions, prices for construction labour, equipment or materials or bidding procedures, AECOM, its directors, officers and employees are not able to, nor do they, make any representations, warranties or guarantees whatsoever, whether express or implied, with respect to such estimates or opinions, or their variance from actual construction costs or schedules, and accept no responsibility for any loss or damage arising therefrom or in any way related thereto. Persons relying on such estimates or opinions do so at their own risk.

Except (1) as agreed to in writing by AECOM and Client; (2) as required by-law; or (3) to the extent used by governmental reviewing agencies for the purpose of obtaining permits or approvals, the Report and the Information may be used and relied upon only by Client.

AECOM accepts no responsibility, and denies any liability whatsoever, to parties other than Client who may obtain access to the Report or the Information for any injury, loss or damage suffered by such parties arising from their use of, reliance upon, or decisions or actions based on the Report or any of the Information ("improper use of the Report"), except to the extent those parties have obtained the prior written consent of AECOM to use and rely upon the Report and the Information. Any injury, loss or damages arising from improper use of the Report shall be borne by the party making such use.

This Statement of Qualifications and Limitations is attached to and forms part of the Report and any use of the Report is subject to the terms hereof.

AECOM: 2015-04-13 © 2009-2015 AECOM Canada ULC All Rights Reserved.

#### **Revision History**

Re	ev#	<b>Revision Date</b>	Revised By:	Revision Description
	0	May 2025	E. Carlson/M. Gaudreau	Draft
	1	June 2025	E. Carlson/M. Gaudreau	Final
	2	July 2025	M. Gaudreau	Final – Revision 1

#### **Distribution List**

# Hard Copies	PDF Required	Association / Company Name
	✓	City of Winnipeg
	✓	AECOM Canada ULC

### **Table of Contents**

1.	Intr	roduction	1
2.	Pro	oject Background	1
3.	Sch	hedule	2
4.	Des	scription of Proposed Works	2
	4.1	Site Development	
	4.2		
	4.3		
	4.4	Downstream Gravity System	4
<b>5</b> .	Enν	vironmental and Human Health Effects	4
6.	Oth	ner Regulatory Requirements	7
7.	Cor	nclusion	7
Tak	oles		
Table	1 - Pro	pject Schedule	2
Table	2 - Pro	oject Environmental Interactions, Mitigation, and Residual Effects	5

#### **Appendices**

Appendix A Design Drawings

#### 1. Introduction

This NoA to the Licence is for the construction of the replacement FGSV Wastewater Siphon Crossings of the Red River as shown in Appendix A. The proposed FGSV Wastewater Siphon Crossing is a like for like replacement designed to maintain the existing level of service as the original crossing, and consists of:

- New discharge chamber replacing the original discharge manhole receiving the pumped flows (unchanged) from the D'Arcy Lift Station.
  - The new discharge chamber will be fitted with an overflow weir set to 227 m, 23 mm higher than the original siphon system's overflow, designed to maintain the level of service up to a 1:100 year summer design rainfall event.
- New 1350 mm RCP gravity sewer connecting the new discharge chamber to the new upstream siphon chamber crossing eastbound Abinojii Mikanah.
- New upstream siphon chamber, configured to allow for siphon isolation and hydrostatic leakage testing.
- Two (2) new 900 mm DR 11 HDPE siphon carrier pipes installed within a new 2100 mm RCP casing pipe tunneled by MTBM across the Red River in underlying bedrock.
- New downstream siphon chamber, configured to allow for siphon isolation and hydrostatic leakage testing.
- New 1350 mm RCP gravity sewer connecting the downstream siphon chamber to a new manhole on the existing St. Vital Trunk Crossing eastbound Abinojii Mikanah.

Key features of the new FGSV are as follows:

- 1. Hydraulic equivalency resulting in no expected change in environmental or human health effects including:
  - a. Overflow volume and occurrence will be limited to that of the original siphon crossing configuration with:
    - i. No overflows occurring for the 1:25 year summer design rainfall event.
    - ii. No increase in overflow volume for a 1:100 summer design rainfall event.
  - b. The upstream level of service against basement flood protection will be maintained.
  - c. The downstream impacts on the St. Vital Trunk System and associated level of service against basement flooding will be maintained.
- 2. The two (2) new 900 mm DR 11 HDPE wastewater siphon crossings will be encased and grouted within a 2100 mm RCP, and further tunnelled within competent bedrock consistent with Clause 20 of the Licence.
- The new upstream and downstream siphon chambers will be fitted with knife gates, vertical pipe extensions to surface and small diameter threaded taps for pressure gauges to allow for hydrostatic leakage testing consistent with Clause 19 of the Licence.

Once the new FGSV Wastewater Siphon Crossings of the Red River are commissioned, the Emergency Bypass System currently in place will be decommissioned and removed.

Additional project background, schedule, description and other regulator requirements are discussed in the following sections.

#### 2. Project Background

During planned inspections in late 2023, the original 700 mm and 800 mm HDPE FGSV Siphons Crossing the Red River were found to be in poor condition, where one (1) of the siphons was assessed to be leaking and put out of service. After the assessment of the siphons, planning was immediately commenced to install an emergency

bypass system across the Red River, via the east bound Fort Garry Road Bridge on Abinojii Mikanah. On February 7, 2024, a sinkhole on the west bank of the river was observed, which indicated the partial collapse and subsequent failure of the second siphon.

The design and implementation of an emergency bypass system began in December 2023 initiated by the discovery of the leaking siphon. Construction on site of the bypass commenced on February 5, 2024, and now consists of a system capable of replicating the existing D'Arcy Lift Station flows to approximately 820 l/s. The pumps connect into two (2) 400 mm DR 17 HDPE emergency bypass force mains, which are routed on the north side of the eastbound Abinojii Mikanah Bridge, and discharge to the original downstream siphon chamber.

The original 700 mm and 800 mm siphons were isolated from the wastewater sewer (WWS) system via structural concrete plugs in February of 2024. Consequently, the siphons were not able to collect and/or leak any additional wastewater to the environment.

These siphons floated twice within the Red River since their isolation from the WWS system in August of 2024 and again in October of 2024. Consequently, in March 2025, the exposed sections along the river bottom have been removed due to waterway navigational hazards. The remaining in-slope sections will be filled with a flowable cement and abandoned. The details of the abandonment of the original siphon crossing are provided in the Notice of Alteration to the Licence dated October 31, 2024.

The proposed new subsurface crossing of the Red River will allow for decommissioning of the Emergency Bypass and restoring the system to the original operation.

#### 3. Schedule

Key milestone dates are presented in Table 1.

Final Acceptance

MilestoneDatePrequalification CloseDecember 23, 2024Tender CloseJune 6, 2025AwardJuly 4, 2025MobilizationSeptember 8, 2025Bypass Decommissioning/New Crossing OnlineMay 15, 2026Total PerformanceJuly 15, 2026

June 15, 2027

**Table 1 - Project Schedule** 

### 4. Description of Proposed Works

The proposed works for the new FGSV Wastewater Siphon Crossings of the Red River are described in the following sections and are shown in the Tender Drawings for City of Winnipeg Tender 1010-2024B (Appendix A).

#### 4.1 Site Development

The Contractor is allocated laydown areas as shown in the Drawings (Appendix A). The following additional requirements for Environmental Protection have been stipulated in the Tender:

- Construction material shall not be stockpiled within 106.7 m of the regulated summer water level of the Red River in accordance with the City of Winnipeg's Waterway By-Law.
- Contractor shall not store or refuel within 100 m of the waterway and shall have a designated Emergency Response Coordinator for any spills.
- Contractor shall provide protection for existing trees and coordinate with the City of Winnipeg's Forestry Department in advance of any tree removal.
- Vegetation clearing, as needed, shall not take place during the breeding bird season for the City of Winnipeg (April 14 to August 28)¹ to avoid contravening bird protection legislation unless conditions and criteria are met for pre-construction nest surveys to determine nest occupancy as stipulated by Environment and Climate Change Canada, and nest protection mitigation is applied for active nests as stipulated by Environment and Climate Change Canada².
- Contractor shall maintain security fencing around the site for public safety and will maintain pedestrian transportation around the work area.

#### 4.2 Upstream Gravity System

The new discharge chamber will collect the flow from the D'Arcy Lift Station, and convey it through a new 1350 mm RCP to the upstream siphon chamber. Similar to the original siphon crossing, the new siphon crossing is fitted with an emergency overflow weir in the discharge chamber, which enables the system to relieve itself through the existing 1350 mm gravity sewer to the Red River during infrequent (e.g. extreme summer rainfall) or unanticipated (e.g. infrastructure failure/blockages) conditions.

Under extreme summer rainfall events, the new FGSV siphon crossing, similar to the original siphon crossing, is only expected to overflow for design events in excess (not including) of the 1:25 year summer design rainfall event. For the 1:100 year summer design rainfall event, the overflow volume with the new FGSV siphon crossing (estimated at 340 m³) is anticipated to be slightly less than the original siphon crossing (estimated at 450 m³) under the same design condition. The impact on basement flooding risk during these extreme conditions is similarly expected to be negligible.

The construction of the new discharge chamber will consist of a tight shoring system to protect against any deleterious movement of the City's Aqueduct. The new discharge chamber will be a cast-in-place reinforced concrete structed fitted with lining to protect against hydrogen sulfide attack.

The new 1350 mm gravity sewer will be tunneled beneath the eastbound Abinojii Mikanah roadway, and consists of lined reinforced concrete pipe connecting to the new upstream siphon chamber.

<sup>&</sup>lt;sup>1</sup> Breeding bird nesting period for Zone B4 as indicated by Environment and Climate Change Canada ( https://www.canada.ca/en/environment-climate-change/services/avoiding-harm-migratory-birds/general-nesting-periods/nesting-periods.html )

<sup>&</sup>lt;sup>2</sup> Environment and Climate Change Canada. Guidelines to avoid harm to migratory birds. <a href="https://www.canada.ca/en/environment-climate-change/services/avoiding-harm-migratory-birds/reduce-risk-migratory-birds.html#toc2">https://www.canada.ca/en/environment-climate-change/services/avoiding-harm-migratory-birds/reduce-risk-migratory-birds.html#toc2</a>

#### 4.3 River Crossing

The new river crossing will consist of an upstream siphon chamber located on the west side of the Red River, and two (2) new 900 mm HDPE lines crossing the Red River discharging into the new downstream siphon chamber on the east side of the Red River.

The upstream chamber will be constructed within the exit shaft, and the downstream siphon chamber will be constructed within the entry shaft of the MTBM operation. Both chambers will be cast-in-place concrete, with protective linings in the wet chamber and fibreglass reinforced pipe through the dry chamber. The dry chambers are fitted with knife gates and vertical piping to allow for isolation of the river crossing, and small diameter taps that can be fitted with pressure gauges. This will allow the City to undertake hydrostatic leakage testing of the crossings by isolating a single 900 mm siphon line for testing, while the other 900 mm siphon continues to convey normal dry weather flow.

The new siphon crossing will consist of the two (2) new 900 mm HDPE siphons installed within a 2100 mm reinforce concrete encasement pipe installed via MTBM. The 2100 mm MTBM will be installed in competent bedrock, with confining pressures to largely exceed any slurry pressure during the installation negating frac-out risk. Once the 2100 mm reinforced concrete pipe is installed, the two (2) new 900 mm HDPE lines will be pulled through the crossing and grouted in place.

#### 4.4 Downstream Gravity System

From the new downstream siphon chamber, a new 1350 mm gravity sewer will convey flow to a new manhole on the existing 1350 mm St. Vital Trunk.

The new 1350 mm gravity sewer, which will be tunneled beneath the eastbound Abinojii Mikanah roadway, consists of lined RCP connecting to the new St. Vital Trunk manhole.

The construction of the new St. Vital Trunk manhole will consist of a tight shoring system to protect against any deleterious movement of the City's Aqueduct. During construction it is expected that a flow through system to convey existing flows through the excavation will be required, or alternately a modification to the Emergency Bypass to connect flows just downstream of manhole connection. Requirements to maintain existing Emergency Bypass flow capacity have been included in the Tender.

The new St. Vital Trunk manhole will be a standard City of Winnipeg pre-cast manhole fitted with a protective liner to protect against hydrogen sulfide attack.

#### 5. Environmental and Human Health Effects

The environmental and human health effects that could result from the proposed changes and potential mitigation measures which could be implemented are described in Table 2.

Table 2 - Project Environmental Interactions, Mitigation, and Residual Effects

Environmental Component	Baseline Condition	Type of Interaction	Project Phase	Required Mitigation	Residual Effect(s)
Air Quality	The City of Winnipeg's air quality is generally considered good to ideal, posing little to no risk to human health. However, air quality does vary and should be monitored through Winnipeg - Air Quality Health Index. Sources of airborne pollutants typically include industrial operations, vehicle and equipment emissions, fires, and other specific activities.	Emissions from equipment  Dust	Construction  Construction	<ul> <li>Contractor to ensure all equipment is in good working order and is maintained throughout project</li> <li>Contractor to ensure all equipment is fitted with standard air emission control devices</li> <li>Avoid unnecessary idling of vehicles and/or heavy machinery</li> <li>Do not burn materials that will negatively affect air quality</li> <li>Comply with all permit conditions issued by Manitoba Environment and Climate Change or other authorities</li> <li>Employ non-toxic dust control measures as required</li> <li>Avoid excavation activities during extremely windy periods</li> <li>Re-vegetate site as required</li> <li>Comply with all permit conditions issued by Manitoba Environment and Climate Change or other authorities</li> </ul>	N/A
Soils	Based on the Geotechnical Baseline Report, the soil profile consists of topsoil black and grey fat clays overlying silt till, and brecciated dolomitic mudstone (bedrock).	Disturbance, compaction, contamination	Construction	<ul> <li>Limit grubbing and excavation operations to designated areas and utilize excavation boxes if possible</li> <li>Vehicles and machinery should use designated access roads/trails, laydown areas to avoid unnecessary compaction</li> <li>Contractor to ensure all equipment is in good working order, is free of fluid leaks, and is well maintained</li> <li>Contractor to implement appropriate erosion and sediment control measures</li> <li>Contractor to ensure storage containers for hazardous goods are equipped with secondary containment</li> <li>Emergency spill kits kept on site and operators properly trained to use them so that any spills can be contained and cleaned up</li> <li>Ensure all fueling is completed well away from waterway (a minimum of 100 m away from waterway as per Tender specifications)</li> <li>All reportable spill quantities will be reported to the Manitoba Conservation Emergency Response Team at 204-944-4888</li> <li>Comply with all permit conditions issued by Manitoba Environment and Climate Change or other authorities</li> </ul>	N/A
Vegetation	The project site consists of landscaping (grass) and common riverbank trees, native grasses, and low shrub cover.	Loss of vegetation	Construction	<ul> <li>Refer to mitigation measures under Soils</li> <li>Make use of natural or existing clearings where possible</li> <li>Ensure appropriate firefighting equipment is on site and serviceable</li> <li>Protect trees near worksite as required to avoid damage</li> <li>Encourage natural regeneration of disturbed sites and/or revegetate site by seeding, tree planting, and shrub planting (in conjunction with City of Winnipeg Forestry, Naturalist Branch, and Parks)</li> </ul>	N/A
Terrestrial Wildlife	The project site provides wildlife habitat as described above for Vegetation.	Loss of wildlife habitat and potential for disturbance or mortality of wildlife (e.g., breeding birds)	Construction	<ul> <li>Mitigation for Soils, Vegetation, Air Quality and Waste Management will be maintained</li> <li>Wildlife are not to be fed or harassed</li> <li>Vegetation clearing, as needed, shall not take place during the breeding bird season for the City of Winnipeg (April 14 to August 28) to avoid contravening bird protection legislation unless conditions and criteria are met for pre-construction nest surveys to determine nest occupancy as stipulated by Environment and Climate Change Canada, and nest protection mitigation is applied for active nests as stipulated by Environment and Climate Change Canada (https://www.canada.ca/en/environment-climate-change/services/avoiding-harm-migratory-birds/reduce-risk-migratory-birds.html#toc2)</li> </ul>	

Environmental Component	Baseline Condition	Type of Interaction	Project Phase	Required Mitigation	Residual Effect(s)
Aquatic Life	The Red River provides year-round habitat for various life stages of approximately 56 fish species (e.g., channel catfish, walleye, muskellunge, northern pike, smallmouth bass, goldeye, mooneye, sauger).  The Mapleleaf mussel may be present in the Red River and is listed as Endangered under <i>The Endangered Species and Ecosystems Act</i> (Manitoba) and as Threatened under the federal <i>Species at Risk Act</i> (SARA).	Disturbance,	Construction	<ul> <li>Site to be restored to preconstruction conditions, including geometry and contours/elevations</li> <li>Limit grubbing and excavation operations to designated areas</li> <li>Vehicles and machinery should use designated access roads/trails, laydown areas</li> <li>Contractor to ensure all equipment is in good working order, is free of fluid leaks, and is well maintained</li> <li>Contractor to ensure storage containers for hazardous goods are equipped with secondary containment</li> <li>Emergency spill kits kept on site and operators properly trained to use them so that any spills can be contained and cleaned up</li> <li>All spills will be reported to the Manitoba Conservation Emergency Response Team at 204-944-4888</li> <li>Contractor to implement appropriate erosion and sediment control measures</li> <li>Comply with all permit conditions issued by Manitoba Environment and Climate Change or other authorities</li> </ul>	N/A
Heritage	As this is a replacement of previous infrastructure in area previously disturbed, there is a low probability of encountering new heritage materials.	Heritage Resources	Construction	<ul> <li>If Contractor discovers any heritage resources during excavation activities, work must be stopped, and the Historic Resources Branch of the Manitoba Government must be contacted immediately at 204-945-2118</li> <li>Heritage resources monitoring will be conducted during construction as required by Manitoba Historic Resources Branch</li> <li>Comply with all permit conditions issued by Manitoba Environment and Climate Change or other authorities</li> </ul>	N/A
Waste Management	City waste collection bins are placed nearby for pedestrian garbage collection	Waste generation	Construction	<ul> <li>Waste must be collected, sorted, transported, and disposed of based on its unique characteristics at a licensed facility</li> <li>Comply with all permit conditions issued by Manitoba Environment and Climate Change or other authorities</li> </ul>	N/A
Socio-Economic	The adjacent Abinojii Mikanah (Route 165) and FGSV Bridge is an important truck, transit and commuter route. The Awasisak Mēskanôw Greenway is located adjacent to Abinojii Mikanah and crosses the FGSV Bridge. It is Winnipeg's longest multiuse trail and an important cyclist and pedestrian path. The land surrounding the work area is mostly vacant park space, with some residential land nearby.	Noice disturbance, traffic management	Construction	<ul> <li>The City will notify adjacent landowners of the upcoming construction or potential traffic disruptions through letter mail. Public concerns may also be communicated through construction using the City's 311 system</li> <li>Accommodation of multiuse trails and construction of temporary multiuse trail will be provided</li> </ul>	N/A

#### 6. Other Regulatory Requirements

Additionally, AECOM has reviewed the other regulatory requirements as listed in below, which will be addressed separate to this NoA:

- Department of Fisheries and Oceans (DFO):
  - No in water work is expected and appropriate erosion and sediment control measures will be implemented. Therefore, DFO Request for Review, SARA permit or Fisheries Act Authorization is not required.
- Transport Canada Approval under the Canadian Navigable Water Act (CNWA) and the Navigation Protection Program (NPP):
  - Under Section 19 (Buried Pipelines) in the Minor Works Order, the work meets the criteria for "Minor Work". AECOM will provide notice of the work through the Government of Canada Project Registry and on the Navigation Protection Program external submission site.
- Endangered Species and Ecosystems Act:
  - As no in water work is expected, application for Exemption under *The Endangered Species and Ecosystems Act* regarding aquatic Species at Risk is not required.
- Heritage Resource Act:
  - A Heritage Resources Impact Assessment (HRIA) is required, which will include monitoring during construction.
- Waterway Permit:
  - AECOM will submit a waterway permit application under the City of Winnipeg's Waterway By-law No. 5888/92 as work is occurring within 106.7 m (350 ft) of the regulated summer water level of the Red River.

#### 7. Conclusion

AECOM has undertaken the design and tendered the replacement FGSV Wastewater Siphon Crossings of the Red River as part of City of Winnipeg Tender 1010-2024B.

The replacement FGSV Wastewater Siphon Crossings of the Red River is designed to be hydraulically equivalent to the original crossing and consequently not expected to have any additional adverse environmental or human health effects, where:

- The overflow occurrences and volumes will be unchanged, if not improved:
  - For the 1:25 summer design rainfall overflows are not expected, which is consistent with the original siphon crossing.
  - The emergency overflow is only intended to operate under extreme conditions, where for the 1:100 summer design rainfall event the overflow volume is expected to be slightly less compared to the original siphon crossing.
- The level of protection against basement flooding in the upstream system will be maintained.
- The downstream impacts on the St. Vital Trunk System and associated risk of basement flooding are expected to be the same.

The two (2) new 900 mm DR 11 HDPE wastewater siphon crossings will be encased and grouted within a 2100 mm RCP, and further tunnelled within competent bedrock consistent with Clause 20 of the Licence.

#### **City of Winnipeg**

Replacement of the Fort Garry-St. Vital Siphon - Notice of Alteration Revision 1

The new upstream and downstream siphon chambers will be fitted with knife gates, vertical pipe extensions to surface and small diameter threaded taps for pressure gauges to allow for hydrostatic leakage testing consistent with Clause 19 of the Licence.

We consequently conclude that the replacement FGSV Wastewater Siphon Crossings of the Red River is consistent with the Licence and poses no significant residual adverse environmental and human health effects.

Ref: 60728226 RPT-2025-07-03-Cow-FGSV-Notice Of Alteration-Final Rev 1-60728226.Docx



# Appendix A

**Design Drawings** 




## THE CITY OF WINNIPEG

WATER AND WASTE DEPARTMENT ENGINEERING DIVISION

REPLACEMENT OF THE FORT GARRY ST VITAL SIPHON

**TENDER 1010-2024B** 



FOR INDEX SEE Q-1001

SHEET 1 OF 32

G-1000

#### **ABBREVIATIONS**

wws	WASTE WATER SEWER
cs	COMBINED SEWER
LDS	LAND DRAINAGE SEWER
PL	PROPERTY LINE
Ę.	CENTER LINE
G.I.S.	GEOGRAPHIC INFORMATION SYSTEM
B.M.	BENCH MARK
TH	TEST HOLE
ELEV	ELEVATION
INV	INVERT
MIN	MINIMUM
MAX	MAXIMUM
SL	STREET LIGHTING
TS	TRAFFIC SIGNALS
ABAND	ABANDONED
BLDG	BUILDING
HSE	HOUSE
CRN	CORNER
OPP	OPPOSITE
C/S OR S/C	CURB STOP
MTS	MANITOBA TELEPHONE SYSTEM
R.O.W.	RIGHT-OF-WAY
WM	WATERMAIN
CULV	CULVERT
MH	MANHOLE
CB	CATCH BASIN
CI	CURB INLET
VERT.	VERTICAL
HORZ.	HORIZONTAL
I.B.	IRON BAR
FIBRE	FIBRE OPTIC
TYP	TYPICAL
X-ING	CROSSING
HYD	HYDRANT
EXIST	EXISTING
N	NORTH
E	EAST
s	SOUTH
w	WEST
W/	WITH
c/w	CONSTRUCTED WITH
CONC	CONCRETE
AC	ASBESTOS CEMENT
VC OR CLAY	VITRIFIED CLAY
CI	CAST IRON
DI	DUCTILE IRON
PVC	POLYVINYL CHLORIDE
HDPE	HIGH DENSITY POLYETHYLENE
PCCP	PRESTRESSED CONCRETE CYLINDER PIPE
FRPMP	FIBRE REINFORCED POLYMER MORTAR PIPE
	THE TRANSPORT OF THE PROPERTY AND THE

#### **GENERAL NOTES:**

LOCATION APPROVED

UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES

#### 1. CONTRACTOR TO PROTECT WATERWAYS, DRAINAGE INFRASTRUCTURE, MULTI-USE PATH, ROADWAYS AND OTHER SURFACE FEATURES FROM SILT WASHOUT BY INSTALLATION OF SILT FENCES.

B.M. Z63-11 Bishop Grandin Bivd. & the E. bank of the Red River, Tbit. on top of N.W. Cor. of gate chamber which is closest to the most Sib. bridge of two bridges ower Red River on Bishop Grandin Biv

ISSUED FOR TENDER

2. SITE IN PROXIMITY TO D'ARCY LIFT STATION WILL BE HANDED OVER TO CONTRACTOR DECEMBER 15TH, 2025 TO ALLOW FOR LINING OF EXISTING 600mm AND 500mm SEWERS AS SHOWN ON DRAWINGS.

DESIGNED

HORIZONTAL

VERTICAL

DATE BY DATE

ADL

<u>HATCH</u>	PATTERNS	<u>3</u>
EXISTING	PROPOSED	DESCRIPTION
		EARTH OR GROUND ABOVE PIPE
		SAND OR OTHER FINE MATERIAL
, pa	7: ************************************	CONCRETE
		WASHED STONE OR GRANULAR MATERIAL
		INTERLOCKING STONE
		METAL
		GRAVEL OR STONE

DRAWING TITLE

DRAWING INDEX, DESIGN NOTES, LEGEND, & ABBREVIATIONS

GENERAL PLAN - CONSTRUCTION & STAGING - WEST BANK

GENERAL PLAN - CONSTRUCTION & STAGING - EAST BANK

PLAN / PROFILE - D'ARCY PUMPING STATION TO MATCHLINE 1+250

PLAN / PROFILE - EXISTING DISCHARGE MANHOLE TO PROPOSED UPSTREAM SIPHON CHAMBER

PLAN / PROFILE - EXISTING DISCHARGE MANHOLE TO SIPHON INLET & OVERFLOW CHAMBERS

PLAN / PROFILE - PROPOSED DOWNSTREAM SIPHON CHAMBER TO 1350 INTERCEPTOR

PLAN / PROFILE - EAST SIDE LAYDOWN AREA - TEMPORARY MULTI-USE PATHWAY

WEST & SOUTH GATE CHAMBER - ROOF SLAB REPLACEMENT - SECTIONS & DETAILS

PLAN / PROFILE - MATCHLINE 1+250 TO 1350 INTERCEPTOR

STANDARD DETAILS - MONITORING AND INSTRUMENTATION

EXISTING SIPHON CHAMBER MODIFICATIONS - SECTIONS & DETAILS

PROPOSED UPSTREAM SIPHON CHAMBER - PLANS & DETAILS

PROPOSED UPSTREAM SIPHON CHAMBER - SECTIONS & DETAILS

PROPOSED DOWNSTREAM SIPHON CHAMBER - PLANS & DETAILS

STRUCTURAL REINFORCING & MISCELLANEOUS DETAILS

DISCHARGE MANHOLE - STRUCTURAL GENERAL NOTES

UPSTREAM SIPHON CHAMBER - STRUCTURAL PLANS

DOWNSTREAM SIPHON CHAMBER - STRUCTURAL PLANS

DISCHARGE MANHOLE - STRUCTURAL PLANS AND SECTIONS

PROPOSED DOWNSTREAM SIPHON CHAMBER - SECTIONS & DETAILS

UPSTREAM SIPHON CHAMBER - STRUCTURAL SECTIONS AND DETAILS

DOWNSTREAM SIPHON CHAMBER - STRUCTURAL SECTIONS AND DETAILS

SITE GRADING PLAN - WEST BANK & EAST BANK

DISCHARGE MANHOLE - SECTIONS & DETAILS

SITE PLAN - WEST BANK

SITE PLAN - EAST BANK

DETAILS 1

DETAILS 2

SITE GRADING DETAILS

PLAN / PROFILE - PROPOSED LDS

**DRAWING INDEX** 

.3

12

13

14

15

16

17

19

20

21

22

23

24

25

26

27

28

29

30

31

32

CITY OF WINNIPEG DRAWING NUMBER

G-1000

G-1001

C-1000

C-1001

C-1002

C-1003

C-1004

C-1005

C-1006

C-1007

C-1008

C-1009

C-4001

C-4002

C-5001

L-1001

L-1002

L-4001

S-1001

S-1002

S-1003

S-1004

S-1005

S-1006

S-1007

S-4001

S-2001

S-2002

S-2003

S-2004

S-2005

S-2006

#### **AECOM** CHECKED APPROVED MGM RELEASED FOR CONSTRUCTION CONSULTANT DRAWING NUMBER R. LUCKY

Tender No: 1010-2024E CONTRACT NUMBER:

LEGEND

DESCRIPTION

WATER PIPE

FIRE HYDRANT CURB STOP REDUCER COUPLING OR SLIDDER BEND - 11.25\*, 22.5\*, 45\*, 90\* VERTICAL BEND ANODE REPAIR MARKER PLUG

SEWER PIPE MANHOLE

CURB INLET

JUNCTION

€ DITCH CULVERT

SURVEY BAR

SURVEY MONUMENT

TREE - DECIDUOUS

TREE - CONIFEROUS

HYDRO POLE

LAMP STANDARD HYDRO POLE W/STREET LIGHTING

> POLE GUY ANCHOR M.T.S. POLE

PEDESTAL OR BOX

CABINET

M.T.S., SHAW, OR VIDEON

TRAFFIC LIGHT STANDARD

STEAM

FIBRE OPTIC

FENCE

EDGE OF PAVEMENT OR GUTTER

EDGE UNPAVED OR GRAVEL ROAD

PROJECTED P.

LOT LINE SIDEWALK - PATHWAY

EASEMENT

EDGE OF BUILDING

MAILBOX

TREE LINE OR BUSH

DESCRIPTION

WATER PIPE

VALVE

TEE OR CROSS

COUPLING OR BEND

REDUCER

END OF PIPE

UNPAVED GROUND SURFACE

PAVED GROUND SURFACE - C PIPE

GUTTER (NORTH AND WEST)

GUTTER (SOUTH AND EAST) & DITCH (NORTH AND WEST) € DITCH (SOUTH AND EAST)

STRUCTURE

MANHOLE OR CATCH BASIN

G-1001

PARKING METER

PLAN VIEW

EXISTING

 $\odot$ 

 $\boxtimes$ 

-----

~~~~

EXISTING

\_\_\_X\_\_\_

8

\_\_\_x\_\_\_x\_\_\_

\_\_\_\_

\_\_\_\_∇

PROFILE

PROPOSED

C======

\_\_\_\_\_

-----

PROPOSED

8

Winnipèg


THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT ENGINEERING DIVISION


REPLACEMENT OF THE SHEET 2 OF 32 FORT GARRY ST VITAL SIPHON CITY DRAWING NUMBER


FOR INDEX SEE G-1001


INDEX PAGE G-1001


FILE PATH: C:\Users\leippia\AppData\Local\Temp\AcPublish\_2416\FILE NAME: 60728226-SHT-00-G-1001.dwg



































DETAIL - 450 FLARED CONCRETE DITCH INLET C/W SAFETY GRATE






#### INSTRUMENT MONITORING SCHEDULE

|  | DESCRIPTION | MONITORING SCHEDULE                                                                                    |
|--|-------------|--------------------------------------------------------------------------------------------------------|
|  | SMP         | DAILY WHEN ADVANCING TUNNEL FACE IS 20m AWAY TO REACH THE INSTRUMENT LOCATION AND 30m PAST THE UTILITY |
|  |             | 1 READING 2 WEEKS AFTER THE TUNNEL PASSES INSTRUMENT LOCATION                                          |





METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED MUMBERS INDICATE METRES

1500 0.0 1000 1:40 10.0 20.0 30.0 10.0 15.0 0.0

1000 1:50 0.0

LOCATION APPROVED UNDERGROUND STRUCTURES SUPV. U/G STRUCTURES

B.M. Z63-11 Bishop Grandin Bivd. & the E. bank of the Red River, Tbit. on top of N.W. Cor. of gate chamber which is closest to the mos bridge of the Red River on Bishop Grandin Bi ISSUED FOR TENDER 25/05/14 ADL VERTICAL DATE BY DATE 2025 05 13

200 MIN. REBAR EMBEDMENT

**AECOM** 

DESIGNED CHECKED BY APPROVED MGM ADL RELEASED FOR CONSTRUCTION HORIZONTAL 1:25

Tender No: 1010-2024B CONTRACT NUMBER:

NGINEER'S SEAL CONSULTANT DRAWING NUMBER

C-5001

Winnipeg

THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT ENGINEERING DIVISION

REPLACEMENT OF THE FORT GARRY ST VITAL SIPHON

FOR INDEX SEE


G-1001


SHEET 15 OF 32 CITY DRAWING NUMBER


STANDARD DETAILS MONITORING AND INSTRUMENTATION

C-5001


FILE PATH: C:\Users\leippia\DC\ACCDocs\AECOM\60728226-Repic-of-FGSV-Siphon\Project Files\900 Design Collaboration\20 Detailed Design\C\SHT\FILE NAME: 60728226-SHT-00-C-5001.dwg











FILE PATH: C:\Users\eippia\DC\ACCDocs\AECOM\60728226-Repic-of-FGSV-Siphon\Project Files\900 Design Collaboration\20 Detailed Design\L\SHT\FILE NAME: 60728226-SHT-00-L-1001.dwg




















## GENERAL NOTES:

- ALL WORK SHALL MEET OR EXCEED MINIMUM REQUIREMENTS OF THE NATIONAL BUILDING CODE OF CANADA 2020, ASSOCIATED STANDARDS REFERENCED IN THAT CODE, AND LOCAL STANDARDS AND BYLAWS AS APPLICABLE.
- READ THE STRUCTURAL DRAWINGS IN CONJUNCTION WITH THE SPECIFICATIONS AND ALL OTHER PERTINENT CONTRACT DOCUMENTS. ENSURE THAT RELEVANT STATUTORY PERMITS HAVE BEEN OBTAINED PRIOR TO COMMENCING SITE WORKS.
- ALL DIMENSIONS ARE IN METRIC UNITS UNLESS NOTED, VERIFY DIMENSIONS PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES TO THE CONSULTANT BEFORE PROCEEDING. DO NOT SCALE DRAWINGS.
- REFER TO ARCHITECTURAL, MECHANICAL, ELECTRICAL, AND PROCESS DRAWINGS FOR LOCATION OF RECESSES, INSERTS, SLEEVES, ETC WHICH MUST BE CAST OR FORMED IN THE CAST-IN-PLACE CONCRETE.
- REFER TO ALL OTHER RELEVANT DRAWINGS (E.G. ARCHITECTURAL MECHANICAL AND ELECTRICAL) FOR LOCATIONS AND DIMENSIONS OF EQUIPMENT BASE, PITS, DEPRESSIONS, OPENINGS, SLEEVES AND OTHER BUILDING COMPONENTS NOT SHOWN ON THE STRUCTURAL DRAWINGS. REPORT DISCREPANCIES TO THE CONSULTANT BEFORE PROCEEDING WITH THE WORK
- CONTRACTOR TO CONFIRM DIMENSIONS AND ALL OTHER CRITICAL DETAILS WITH EQUIPMENT SUPPLIERS PRIOR TO CONSTRUCTION. REPORT 10 SCREPANCIES, AND OBTAIN APPROVAL PRIOR TO PROCEEDING WITH CONSTRUCTION.
- DO NOT RELY ON ACCURACY OF ANY AS-BUILT RECORDS PROVIDED. SURVEY AND VERIFY ACTUAL DIMENSIONS AND LAYOUT.
- NOTIFY THE STRUCTURAL ENGINEER OF RECORD 48 HOURS IN ADVANCE FOR SITE REVIEW OF STRUCTURAL WORK.
- THE STRUCTURAL DRAWINGS HEREIN REPRESENT THE FINISHED STRUCTURE. THE CONTRACTOR SHALL PROVIDE ALL TEMPORARY GUYING, BRACING, AND SHORING REQUIRED TO ERECT AND HOLD THI STRUCTURE IN PROPER ALIGNMENT UNTIL ALL STRUCTURAL WORK AND CONNECTIONS HAVE BEEN COMPLETED. THE INVESTIGATION, DESIGN. ADEQUACY, AND INSPECTION OF ERECTION BRACING, SHORING TEMPORARY SUPPORTS, ETC, ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE DESIGNED BY A PROFESSIONAL ENGINEER REGISTERED IN THE PROVINCE OF MANITOBA
- 10. DRAWINGS INDICATE GENERAL AND TYPICAL DETAILS OF CONSTRUCTION, WHERE CONDITIONS ARE NOT SPECIFICALLY SHOWN, SIMILAR DETAILS OF CONSTRUCTION SHALL BE USED, SUBJECT TO THE APPROVAL OF THE CONSULTANT.
- ALL STRUCTURAL SYSTEMS WHICH ARE TO BE COMPOSED OF COMPONENTS TO BE FIELD ERECTED SHALL BE SUPERVISED BY THE SUPPLIER DURING MANUFACTURING, BELIVERY, HANDLING, STORAGE, AND ERECTION IN ACCORDANCE WITH THE SUPPLIER'S INSTRUCTIONS
- 12. LOADING APPLIED TO THE STRUCTURE DURING THE PROCESS OF CONSTRUCTION SHALL NOT EXCEED THE SAFE LOAD-CARRYING CAPACITY OF THE STRUCTURAL MEMBERS. DESIGN LOADS ARE INDICATED WITHIN THESE NOTES. DO NOT APPLY CONSTRUCTION LOADS UNTIL STRUCTURAL FRAMING IS PROPERLY CONNECTED AND TEMPORARY BRAGNIC IS NOT APPLY. TEMPORARY BRACING IS IN PLACE.
- 13. SUBMITTALS:
  - SUBMIT THE FOLLOWING SHOP DRAWINGS, SEALED BY A QUALIFIED PROFESSIONAL ENGINEER REGISTERED IN THE PROVINCE OF MANITOBA. PRIOR TO FABRICATION: A) SHORING
  - B) CONCRETE MIX DESIGNS
  - D) CONCRETE REINFORCING
  - 2. FULLY DETAIL SHOP DRAWINGS SHOWING ALL INFORMATION FULLY DETAIL SHOP DRAWINGS SHOWING ALL INFORMATION NECESSARY FOR FABRICATION AND INSTALLATION IN ACCORDANCE WITH INDUSTRY STANDARDS, ALL SHOP DRAWING SUBMITTALS TO BE IN METRIC UNITS INCLUDING DIMENSIONS, REINFORCING, BOLTS, AND STRUCTUR.
  - IMPROPERLY PREPARED SHOP DRAWINGS ARE SUBJECT TO REJECTION AND, ON THAT BASIS, ARE TO BE WITHDRAWN AND RESUBMITTED.
  - DO NOT COMMENCE FABRICATION UNTIL REVIEWED SUBMITTAL. HAS BEEN RETURNED, REVIEW OF SUBMITTALS DOES NOT RELIEVE THE CONTRACTOR FROM COMPLIANCE WITH THE CONTRACT DOCUMENTS.
- 14. REPORT TO THE CONSULTANT ALL WORKS THAT DO NOT COMPLY WITH THE PROJECT REQUIREMENTS AND SUBMIT REMEDIAL WORKS PROPOSAL FOR COMMENT / AGREEMENT. DEFECTIVE WORK AND SUBSTANDARD MATERIALS SHALL BE RECTIFIED SATISFACTORILY OR
- 15. SUBMIT METHOD STATEMENTS TO CONSULTANTS WHEN REQUESTED FOR INFORMATION / COMMENT / AGREEMENT
  - CONTRACTOR'S QUALITY / INSPECTION PROCEDURES
  - CONCRETE REPAIR PROCEDURES

500

5.0

1:25

1000

10.0

1500 0.0

15.0 0.0

1:40

- HOT / COLD WEATHER CONCRETING PROCEDURE

**METRIC** 

500

2000

30.0

20.0

1000

1:50

0.0

2000

25.0

3000

50.0

250

1000

10.0

#### DESIGN CRITERIA

- DESIGN STANDARDS: RRDS:
  NATIONAL BUILDING CODE OF CANADA, 2020
  E: CSA STANDARDS A23.1, A23.2 AND A23.3
  RAL STEEL: CSA STANDARD S16
  ONS: GEOTECHHOCAL INVESTIGATION AND REPORT
  BY: GEOTECH DATA REPORT DATED APRIL 11, 2025.
- IMPORTANCE CATEGORY: POST DISASTER

DEAD LOADS: SELF WEIGHT ADDITIONAL LOADS: REFER TO PLANS
LIVE LOADS: REFER TO PLANS IMPORTANCE FACTORS: Is = 1.25 SNOW LOADS: (ULS), 0.9 (SLS) GROUND SNOW LOAD: Ss = 1.9 ASSOCIATED RAIN LOAD

#### SNOW LOAD FACTORS Cb. Cw. Cs. Ca. AND DRIFT LOADS IN ACCORDANCE WITH THE NATIONAL BUILDING CODE OF CANADA 2020.

- PROVIDE SHORING AS INDICATED ON THE DRAWINGS AND WHERE REQUIRED TO MEET OCCUPATION HEALTH AND SAFETY REQUIREMENTS.
- REFER TO CONTRACT SPECIFICATIONS
- SHORING SHALL BE DESIGNED BY AND BEAR THE SEAL OF A QUALIFIED PROFESSIONAL ENGINEER REGISTERED IN THE PROVINCE OF MANITOBA. SUBMIT TO CONSULTANT FOR REVIEW.
- REMOVE THE TOP OF SHORING TO A MINIMUM DEPTH OF 1.5 m BELG FINISHED GRADE AFTER COMPLETION OF FOUNDATION WALL BACKFUNLESS OTHERWISE STATED IN CONTRACT SPECIFICATIONS.

- REFER TO SPECIFICATION SECTION E16 EXCAVATION AND BACKFILL.
- ENSURE THAT THE INTEGRITY OF EXISTING UNDERGROUND SERVICES / STRUCTURES ARE MAINTAINED AT ALL TIMES DURING THE WORK, REPAIR. RECTIFY IMMEDIATELY ANY DAMAGE / DISRUPTION TO THE CLIENT'S SATISFACTION AND AT THE CONTRACTOR'S OWN COST
- EXCAVATIONS SHALL BE IN ACCORDANCE WITH APPLICABLE OCCUPATIONAL HEALTH AND SAFETY REGULATIONS.
- THE CONTRACTOR SHALL THAT MAINTAIN A DRY EXCAVATION DURING THE ENTIRE PERIOD OF CONSTRUCTION.
- BACKFILL MATERIALS AS SHOWN ON DRAWINGS
- TO AVOID DIFFERENTIAL LATERAL PRESSURES, BACKFILL SHALL BE BROUGHT UP EVENLY AROUND THE WALLS. ONLY HAND OPERATED COMPACTION SHOULD BE EMPLOYED WITHIN 600 mm OF THE CONCRETE
- BACKFILLING SHALL NOT BE COMPLETED UNTIL THE MAIN FLOOR SLAB HAS ACHIEVED 70% OF THE DESIGN COMPRESSIVE STRENGTH.
- DO NOT PLACE BACKFILL ON FROZEN GROUND OR WATER LOGGED GROUND, NOR USE FROZEN MATERIAL.
- MAINTAIN TO WITHIN +/- 1% OPTIMUM MOISTURE CONTENT TO PERMIT COMPACTION TO ATTAIN SPECIFIED DENSITIES. PROTECT BACKFILLED GRADE DURING AND AFTER COMPLETION OF BACKFILL OPERATION FROM SOFTENING DUE TO EXCESS MOISTURE.
- 10. FENCE OFF OR MAKE INACCESSIBLE ALL EXCAVATIONS IF LEFT

## RAFT FOUNDATIONS

- RAFT FOUNDATION SLABS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE RECOMMENDATIONS PROVIDED IN THE GEOTECHNICAL REPORT.
- THE RAFT FOUNDATION SHALL BE FOUNDED ON UNDISTURBED COMPETENT, NATURALLY DEPOSITED GLACIAL TILL THAT IS ADEQUATELY PROTECTED FROM FREEZING. WETTING, SOFTENING AND DISTURBANCE. THE BEARING SOIL SHOULD BE INSPECTED AND APPROVED BY QUALIFIED GEOTECHNICAL PERSONNEL
- TO PRESERVE SOIL DENSITY AND TO MINIMIZE DISTURBANCE TO THE FOUNDING SOILS, PLACE MINIMUM 100 mm THICK LEAN MIX CONCRETE SLABS BELOW THE RAFT SLABS.
- DISTURBED FOUNDATION SOILS, AND SOILS EXPOSED TO FREEZING OR WETTING SHALL BE REMOVED AND REPLACED WITH LEAN MIX CONCRETE FILL,

- PROTECT THE PREPARED FOUNDATION SOILS AND MUD SLAB FROM FREEZING PRIOR TO, DURING AND AFTER CONSTRUCTION
- RAFT SLABS HAVE BEEN DESIGNED FOR THE FOLLOWING LIMIT STATES DESIGN PARAMETERS

# DOWNSTREAM (EAST) SIPHON CHAMBER

GEOTECHNICAL RESISTANCE FACTOR: 0.5 FACTORED BEARING RESISTANCE: 500 kPa SERVICEABILITY LIMIT PRESSURE: UPLIFT PRESSURE DUE TO BUOYANCY 102.9 kPa

#### GEOTECHNICAL RESISTANCE FACTOR: 0.5 FACTORED BEARING RESISTANCE: 190 kPa SERVICEABILITY LIMIT PRESSURE: 170 kPa UPLIFT PRESSURE DUE TO BUOYANCY 34,3 kPa

### DISCHARGE CHAMBER:

UPSTREAM (WEST) SIPHON CHAMBER:

GEOTECHNICAL RESISTANCE FACTOR: 0.5 FACTORED BEARING RESISTANCE: 159 kPa SERVICEABILITY LIMIT PRESSURE: 150 kPa UPLIFT PRESSURE DUE TO BUOYANCY 14.1 kPa

#### FOUNDATION WALLS

FOUNDATION WALLS HAVE BEEN DESIGNED FOR LATERAL EARTH PRESSURES DETERMINED IN ACCORDANCE WITH THE FOLLOWING:

WHERE: K = 0.71 y = 18 kN / m3 q = 12 kPa

- 2. BACKFILL MATERIALS AS SHOWN ON DRAWINGS.
- TO AVOID DIFFERENTIAL LATERAL PRESSURES, BACKFILL SHALL BE BROUGHT UP EVENLY AROUND THE WALLS. ONLY HAND OPERATED COMPACTION SHOULD BE EMPLOYED WITHIN 600 mm OF THE FOUNDATION WALLS.
- BACKFILL WITHIN 600 mm OF THE FOUNDATION WALLS SHALL BE COMPACTED TO 95 PERCENT OF THE SPMDD (STANDARD PROCTOR MAXIMUM DRY DENSITY). THIS MATERIAL SHALL NOT
- BACKFILLING SHALL NOT BE COMPLETED UNTIL THE FLOOP SLAB AND STRUCTURE ARE COMPLETE AND HAVE ACHIEVED 70% OF THE DESIGN COMPRESSIVE STRENGTH.

#### CONCRETE REINFORCING

- REFER TO SPECIFICATION SECTIONE24 REINFORCING STEEL.
- REINFORCING WORK SHALL BE IN ACCORDANCE WITH CSA A23.1, ACI 315, AND THE RSIC REINFORCING STEEL MANUAL OF STANDARD PRACTICE.
- ALL REINFORCING TO BE CONTINUOUS. SPLICE ONLY AS DETAILED OR APPROVED BY THE CONSULTANT. UNLESS DETAILED OTHERWISE, ALL LAP SPLICES SHALL BE CLASS B
- WHERE NOT SPECIFICALLY DETAILED, REINFORCING STEEL SHALL BE PROTECTED BY CONCRETE COVER AS FOLLOWS CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH: 75mm
- MATERIALS SHALL CONFORM TO THE FOLLOWING: REINFORCING STEEL: CSA G30,18, GRADE 400, PLAIN FINISH, DEFORMED BARS

WELDABLE REINFORCING STEEL: CSA G30.18, GRADE 400W PLAIN FINISH, DEFORMED

SUBMIT REINFORCING STEEL SHOP DRAWINGS TO THE CONSULTANT FOR REVIEW PRIOR TO FABRICATION.

OTHERWISE: 60mm

- CHAIR SLAB REINFORCING NOT FURTHER THAN 1000mm IN EITHER DIRECTION. SUPPLY SUPPORT BARS, CHAIRS, AND CARRIERS AS NECESSARY.
- DOWELS AND ANCHOR BOLTS SHALL BE SECURED IN POSITION. BY MEANS OF TEMPLATES BEFORE CONCRETE IS POURED.
  WHERE DOWELS OR ANCHOR BOLTS ARE TO BE EXPOSED FOR ONGER THAN 1 MONTH AFTER INSTALL ATION, PROVIDE WRAPPING AND COVERING AS PROTECTION
- 90° HOOKS AND 180° HOOKS WHERE SHOWN SHALL BE DETAILED AS STANDARD HOOKS UNLESS NOTED OTHERWISE
- 10. REPLACE BARS THAT DEVELOPED SPLITS OR CRACKS
- 11. REINFORCING SHOWN ON STRUCTURAL DETAILS ARE SCHEMATIC ONLY AND MAY NOT SHOW THE ACTUAL NUMBER OF REBARS.

ISSUED FOR TENDER

### CONCRETE ACCESSORIES

- APPLY APPROVED NON-METALLIC HARDENER OR SEALER TO AREAS SHOWN ON ARCHITECTURAL FLOOR FINISH SCHEDULE, HARDENER AND SEALER SHALL BE FROM SAME MANUFACTURER (TARGET, GRACE, STERNSON, MASTER BULDERS OR DIAMEG). HARDENER AGGREGATE SHALL BE APPLIED IN TWO SHAKES TO 4.0 KG/SQ M, TO MANUFACTURERS RECOMMENDATIONS.
- GROUT: NON-SHRINK, NON-METALLIC GROUT WITH MINIMUM STRENGTH AT THREE DAYS OF 20 MPA AND MINIMUM STRENGTH AT 28 DAYS OF 40 MPA. EPOXY GROUT SHALL BE USED FOR VIBRATING EQUIPMENT BASE WHERE SPECIFIED. APPLY GROUT STRICTLY IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
- 3. BONDING AGENTS: THREE COMPONENT, WATER BASED, EPOXY RESIN / CEMENT BONDING AGENT
- ASPHALTIC FIBREBOARD: ASPHALT SATURATED FIBRE BOARD CONFIRMING
- 5. STEEL BAR SUPPORT/CHAIRS: GALVANIZED/STAINLESS STEEL OR PLASTIC. DO NOT USE ROCK, BRICKS OR CONCRETE FRAGMENTS.
- 6. INSULATION: RIGID STYROFOAM HI-40 BY DOW OR APPROVED EQUIVALENT.
- CURING COMPOUNDS SHALL NOT BE USED OVER CONCRETE SURFACE DESIGNATED TO RECEIVE PROTECTION COATING OR PAINTED FINISH

#### CAST-IN-PLACE CONCRETE

GROUT

- REFER TO SPECIFICATION SECTIONS E23 CAST-IN-PLACE CONCRETE, E25 CONCRETE PROTECTIVE LINERS.
- 2. CAST-IN-PLACE CONCRETE WORK SHALL BE IN ACCORDANCE WITH CSA
- MATERIALS SHALL CONFORM TO THE FOLLOWING: CEMENT CSA A23.1/A23.2 WATER

CSA A23.1/A23.2 AIR ENTRAINING ADMIXTURE TO ASTM C260 ADMIXTURES: CHEMICAL ADMIXTURES TO ASTM C494 WATERPROOFING ADMIXTURE:

SPG VAPOR LOCK 20/21 PREMIXED. NON-SHRINK NON-METALLIC GROUT WITH MINIMUM STRENGTH AT 4 DAYS OF 20 MPa, AND AT 28 DAYS OF 40

- SUPPLEMENTARY CEMENTING MATERIALS WITH A MAXIMUM OF 20 PERCENT TYPE F FLY ASH REPLACEMENT BY MASS OF TOTAL CEMENTITIOUS MATERIALS, IN ACCORDANCE WITH CSA A3001, IS PERMITTED.
- THE USE OF ACCELERATING OR SET RETARDING ADMIXTURES DURING HOT AND COLD WEATHER SHALL BE APPROVED BY THE CONSULTANT. ADMIXTURES CONTAINING CALCIUM CHLORIDE ARE NOT PERMITTED.
- CONCRETE MIXES SHALL BE DESIGNED TO MEET THE FOLLOWING PERFORMANCE CRITERIA IN ACCORDANCE WITH CSA A23,1 TABLE 5, ALTERNATIVE 1:

| TY       | CSA<br>EXPOSURE<br>CLASS | CEMENT<br>TYPE | MINIMUM<br>COMPRESSIVE<br>STRENGTH<br>(MPa) | MAX<br>W/C<br>RATIO | MAX<br>AGGREGATE<br>SIZE<br>(mm) | AIR<br>CONTENT<br>RANGE<br>(%) | WATERPROOFING<br>ADMIX | LOCATION                                                                                                                                           |
|----------|--------------------------|----------------|---------------------------------------------|---------------------|----------------------------------|--------------------------------|------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------|
| <i>'</i> | S-1                      | HS/HSb         | 35 AT 28<br>DAYS                            | 0.4                 | 20                               | 5-8                            | NO                     | DISCHARGE ROOF SLAB, WALLS, RAFT SLAB. DOWNSTREAM SIPHON CHAMBER ROOF SLAB, WALLS, RAFT SLAB. UPSTREAM SIPHON CHAMBER ROOF SLAB, WALLS, RAFT SLAB. |
| E        | -                        | GUL            | 1.5-2.5 AT<br>28 DAYS                       | 1                   | 5                                | ~ 20                           | -                      | IF APPLICABLE,<br>FLOWABLE<br>CEMENT<br>STABILIZED FILL<br>AROUND<br>CHAMBERS                                                                      |

- 7. CONCRETE FOR ROOF SLABS AND BEAMS SHALL HAVE NO ARTIFICIALLY ENTRAINED AIR.
- WATERPROOFING ADMIX SHALL BE ADDED TO CONCRETE MIX TYPE A AT THE TIME OF BATCHING IN ACCORDANCE WITH THE MANUFACTURES
- SUBMIT CONCRETE MIX DESIGNS TO THE CONSULTANT FOR REVIEW PRIOR TO COMMENCEMENT OF WORK.
- ENSURE REINFORCEMENT AND INSERTS ARE NOT DISTURBED DURING CONCRETE PLACEMENT. DO NOT PLACE CONCRETE AGAINST FROZEN GROUND OR IN STANDING WATER.
- CONCRETE TO BE BATCHED AND COMPLETELY DISCHARGED IN A PERIOD NOT EXCEEDING NINETY (90) MINUTES FROM THE TIME OF INITIAL ADDITION OF WATER TO THE CEMENT AND AGGREGATE.
- 12. HORIZONTAL CONSTRUCTION JOINTS IN FOUNDATION WALLS ARE NOT PERMITTED UNLESS AUTHORIZED OR SPECIFIED BY THE CONSULTANTS.
- 13. USE 25 x 25 FORMED CHAMFERS ON EXPOSED CORNERS OF BEAMS COLUMNS AND WALLS U.N.O.

- 14. MAINTAIN ACCURATE RECORDS OF POURED CONCRETE ITEMS TO INDICATE DATE, LOCATION OF POUR, AIR TEMPERATURE, AND TEST SAMPLES TAKEN. SUBMIT RECORDS TO ENGINEER UPON REQUEST.
- PROTECT CONCRETE FROM PREMATURE DRYING. CURE CONCRETE IN ACCORDANCE WITH CSA-A23.1. PROVIDE ADDITIONAL CURING MEASURES OR PROTECTION DURING HOT OR COLD WEATHER IN ACCORDANCE WITH CSA-A23.1.
- 16. DO NOT PLACE CONCRETE WHEN WEATHER IS NOT SUITABLE (E.G. DURING RAIN, SNOW) UNLESS ADEQUATE PRECAUTIONARY MEASURES ARE IN PLACE.
- 17. FILL TIE HOLES IN ACCORDANCE WITH CSA-A23.1.
- 18. REPAIR HONEYCOMBED AND DEFECTIVE CONCRETE AT CONTRACTOR'S OWN COST. PROPOSED METHOD STATEMENT AND MATERIAL FOR REPAIR SHALL BE SUBMITTED TO THE CONSULTANT FOR APPROVAL.

#### CONCRETE TESTING

- INSPECTION AND TESTING OF CONCRETE MATERIALS WILL BE CARRIED OUT BY AN INDEPENDENT TESTING LABORATORY DESIGNATED AND PAID FOR BY THE OWNER, IN ACCORDANCE
- A STRENGTH TEST WILL CONSIST OF THREE (3) STANDARD CYLINDERS; ONE TESTED AT SEVEN (7) DAYS, AND TWO TESTED AT TWENTY-EIGHT (28) DAYS.
- A STRENGTH TEST FOR CONCRETE WITH 56-DAY STRENGTH SPECIFIED MILL CONSIST OF FOUR CYLINDERS; ONE TESTED AT SEVEN (7) DAYS, ONE TESTED AT TWENTY-EIGHT (28) DAYS, AND TWO TESTED AT FIFTY-SIX (66) DAYS.
- FREQUENCY OF CONCRETE TESTING WILL BE ONE SET OF CYLINDERS FOR EVERY 50 CUBIC METERS OR PART THEREOF OF EACH CONCRETE MIX POURED IN A DAY. THIS FREQUENCY MAY BE INCREASED OR DECREASED AT THE ENGINEER'S
- 5. TEST SLUMP AND AIR CONTENT EACH TIME CYLINDER SAMPLES ARE TAKEN. FOR CLASS F.1. C-X6. C-1 AND C-2 CONCRETE EVERY LOAD OR BATCH OF CONCRETE SHALL BE TESTED FOR
- THE TESTING LABORATORY WILL TAKE ADDITIONAL CYLINDERS DURING COLD WEATHER CONCRETING. CURE CYLINDERS ON JOB SITE UNDER SAME CONDITIONS AS CONCRETE WHICH THEY
- CONTRACTOR SHALL PROVIDE ACCESS TO ALL WORK BEING INSPECTED/TESTED.
- NON-DESTRUCTIVE METHODS OF TESTING CONCRETE SHALL BE IN ACCORDANCE WITH CSA-A23.2.
- INSPECTION OR TESTING BY TESTING LABORATORY WILL NOT AUGMENT OR REPLACE CONTRACTOR QUALITY CONTROL NOR RELIEVE HIM OF HIS CONTRACTUAL RESPONSIBILITY.
- 10. CONCRETE FAILING TO MEET THE SPECIFIED REQUIREMENTS SHALL BE RETESTED, STERNGTHENED, OR REJECTED IN ACCORDANCE WITH THE CSA-A32. ALL ADDITIONAL TESTING, STRENGTHENING, AND/OR REPLACEMENT SHALL BE AT THE CONTRACTOR'S EXPENSE.

FOR INDEX SEE G-1001



THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT ENGINEERING DIVISION

REPLACEMENT OF THE FORT GARY ST VITAL SIPHON DISCHARGE MANHOLE

STRUCTURAL GENERAL NOTES

SHEET 27 OF 32

S - 2001

CITY DRAWING NUMBER

LOCATION APPROVED AECOM UNDERGROUND STRUCTURES INSTRUCTION COMPLETION DATE: YYYY MM D SUPV. U/G STRUCTURES COMMITTEE DESIGNED CHECKED KB APPROVED MRK ΜВ

2025 05 14

HORIZONTAL AS NOTED

MRK VERTICAL


R. LUCKY


RELEASED FOR CONSTRUCTION


S-2001


FILE PATH: C:\Users\mark.kalanack\DC\ACCDocs\AECOM\60728226-Repic-of-FGSV-Siphon\Project Files\900 Design Collaboration\20 Detailed Design\S\SHT\FILE NAME: 60728226-SHT-00-S-1003\_S-2001.dwg


# DATE BY DATE















AECOM Canada ULC 99 Commerce Drive Winnipeg, MB R3P 0Y7 Canada

T: 204.477.5381 F: 431.800.1210 aecom.com

VIA EMAIL (barsha.sagan@gov.mb.ca)

July 24, 2025

Barsha Sagan
Environmental Approval Branch
Environmental and Climate Change
14 Fultz Boulevard
Winnipeg, MB R3Y 0L6

Project # Client Reference:

1

60728226 1069.10

Subject: NOA - City of Winnipeg - SEWPCC - Fort Garry-St. Vital Siphon Replacement -

File No. 1069.10

Dear Ms. Sagan:

This letter is in response to the queries received from the Environmental Approvals Branch date July 24, 2025.

Question 1. How will the excavated material from MTBM activities be managed during the construction period?

The Contractor will be responsible for disposing excavated materials off-site at a suitable location as follows. The disposal of excavated materials will be completed in accordance with City of Winnipeg Tender 1010-2024B:

- Remove muck and excavated material from the project site and dispose of spoil as noted below.
- Locate and acquire a site for the legal disposal of muck and excess excavated material and dispose of same in accordance with all applicable laws and regulations.

Question 2. Should any excavation dewatering activities be required during the construction period, how will the water be managed?

The Contractor will not be allowed to dewater the underlying aquifer, and only permitted to dewater the excavation due to seepage from overburden soils, silt and sand seams, or from existing trench bedding and backfill. The management of excavation dewatering will be completed in accordance with City of Winnipeg Tender 1010-2024B:

- The Contractor is responsible for the control, diversion, storage and pumping of all water including
  without limitation rain, snow melt, groundwater, leaking infrastructure and water in pipes throughout all
  stages of the Work.
- Do not pump or drain any water containing excessive suspended materials or harmful substances into
  waterways, sewers or other drainage systems. Control disposal or runoff of water containing suspended
  materials or other harmful substances in accordance with the governing authority's limitations and
  requirements.
- Dispose of all water drained or pumped as above by discharging it into sewers, drainage ditches or
  natural water courses as reviewed by the Contract Administrator, and in compliance with all local,
  Municipal, Provincial and Federal environmental regulations, ordinances, bylaws, etc., and provide
  documentation indicating that authority has been granted to discharge effluent water into any drainage
  ditch, brook, creek or river. The Contractor shall develop and implement at their own cost any filtration,
  settlement or other acceptable treatment methods required prior to disposal.



We trust the above is satisfactory.

Sincerely,

# **AECOM Canada ULC**



Mike Gaudreau, P. Eng. Municipal Engineer Conveyance, Water MG/pab

cc: C. Wiebe, City of Winnipeg, WWD (cwiebe@winnipeg.ca)

R. Lucky, City of Winnipeg WWD (ryanlucky@winnipeg.ca)

M. McDonald, AECOM

M. Krentz, AECOM